

| | | | | |
|-----------------------|-------------|----------|------------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 94 | 2003-071 RS | COOK | 91 | 4 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. 1 | | ILLINOIS | FED. AID PROJECT | |

SUMMARY OF QUANTITIES
URBAN
901.FED./101.STATE

| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | NB ROADWAY 1000 | SB ROADWAY 1000 | DRAINAGE 1000 | BRIDGES X031-2A |
|---------------------|--|-----------------|------------------|-----------------|-----------------|----------------|-----------------|
| 20800150 | TRENCH BACKFILL | CU YD | 134 | | | 134 | |
| 21400100 | GRADING AND SHAPING DITCHES | FOOT | 150 | 150 | | | |
| 35102400 | AGGREGATE BASE COURSE, TYPE B, 12" | SO YD | 134 | | | 134 | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 420 | 207 | 213 | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGE WAYS | TON | 98 | 49 | 49 | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 4 | 2 | 2 | | |
| 40600982 | HOT-MIX SURFACE REMOVAL - BUTT JOINT | SO YD | 2340 | 1170 | 1170 | | |
| 40600985 | PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT | SO YD | 1660 | 834 | 834 | | |
| 40603085 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 | TON | 24,999 | 12151 | 12848 | | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 18,276 | 8877 | 9399 | | |
| 44000100 | PAVEMENT REMOVAL | SO YD | 134 | | | 134 | |
| 44200553 | CLASS A PATCHES, TYPE II, 10 INCH | SO YD | 349 | 104 | 245 | | |
| 44200557 | CLASS A PATCHES, TYPE III, 10 INCH | SO YD | 68 | | 68 | | |
| 44200559 | CLASS A PATCHES, TYPE IV, 10 INCH | SO YD | 1234 | 907 | 327 | | |
| 44201765 | CLASS D PATCHES, TYPE II, 10 INCH | SO YD | 730 | 392 | 338 | | |
| 44201769 | CLASS D PATCHES, TYPE III, 10 INCH | SO YD | 380 | 254 | 126 | | |
| 44201771 | CLASS D PATCHES, TYPE IV, 10 INCH | SO YD | 2169 | 1844 | 325 | | |
| 44201296 | DEFORMED BARS - EXPANSION JOINT | EACH | 236 | 236 | | | |
| 44213000 | PATCHING REINFORCEMENT | SO YD | 3656 | 2660 | 996 | | |
| 44213200 | SAW CUTS | FOOT | 11076 | 6726 | 3990 | 360 | |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 1,705 | 851 | 854 | | |
| 48203037 | HOT-MIX ASPHALT SHOULDERS, 10" | SO YD | 134 | | | 134 | |
| 50102400 | CONCRETE REMOVAL | CU YD | 25.7 | | | | 25.7 |
| 50157300 | PROTECTIVE SHIELD | SO YD | 873 | | | | 873 |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 29.8 | | | | 29.8 |
| 50300260 | BRIDGE DECK GROOVING | SO YD | 791 | | | | 791 |
| 50300300 | PROTECTIVE COAT | SO YD | 83 | | | | 83 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 4,330 | | | | 4,330 |
| 50800515 | BAR SPLICERS | EACH | 52 | | | | 52 |
| 52000110 | PREFORMED JOINT STRIP SEAL | FOOT | 240 | | | | 240 |
| 55021600 | RCCP CL III, TYP 2, REIN. CONC. CULVERT, ST. DRAIN, AND SEWER PIPE, CLASS III 12" | FOOT | 130 | | | 130 | |
| 59000200 | EPOXY CRACK INJECTION | FOOT | 200 | | | | 200 |

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES F.A.I. 94 (I-94) |
|-----------|------|--|
| NAME | DATE | |
| | | SCALE: _____ DATE MAY 2007 DRAWN BY DCS CHECKED BY _____ |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

Rev.

PLOT DATE = 5/23/2007
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 USER NAME = #PLOT#