

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2003-071 RS	COOK	91	5
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

URBAN
901.FED.101.STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	NB ROADWAY 1000	SB ROADWAY 1000	DRAINAGE 1000	BRIDGES X031-2A
60202215	CATCH BASINS, TYPE A, 4'-DIAMETER, WITH MEDIAN INLET (604101)	EACH	1	1			
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	12			12	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	560			560	
63500105	DELINEATORS	EACH	1498	693	805		
64200105	SHOULDER RUMBLE STRIP	FOOT	124,562	62239	62323		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	20	10	10		
67100100	MOBILIZATION	L SUM	1	0.4	0.4		0.2
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3200	1600	1600		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	450	225	225		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	450	225	225		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	139,745	68540	71205		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	25,536	11193	14343		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	6,619	3108	3511		
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	35,187	17631	17556		
* 78008210	POLYUREA PAVEMENT MARKING, TYPE 1, 4"	FOOT	70,129	35,065	35,064		
* 78008220	POLYUREA PAVEMENT MARKING, TYPE 1, 5"	FOOT	17,658	8829	8829		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	5193	2597	2596		
* 78200510	BARRIER WALL MARKERS, TYPE A	EACH	627	314	313		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	61,908	30,954	30,954		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	5193	2597	2596		
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,000	1,000			
X0321744	SILICONE BRIDGE JOINT SEALER, 2"	FOOT	66				66
X0322247	MAINTENANCE OF EXISTING TRAFFIC SURVEILLANCE	L SUM	1	0.5	.5		
* X0322300	ELECTRIC CABLE IN CONDUIT NO.18 4/C, TWISTED, SHIELDED	FOOT	10,133	10,133			
X0322729	MATERIAL TRANSFER DEVICE	TON	35986	18014	17972		
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	2				2
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	3,292	876	2416		
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	50				50
X0325428	CLASS A PATCHES, TYPE II, 10 INCH (SPECIAL)	SQ YD	336	179	157		
X0325429	CLASS A PATCHES, TYPE III, 10 INCH (SPECIAL)	SQ YD	156	84	72		
X0325430	CLASS A PATCHES, TYPE IV, 10 INCH (SPECIAL)	SQ YD	1,514	1387	127		
X0325815	REMOVE EXISTING CABLE	FOOT	15,167	15,167			

* SPECIALTY ITEMS

PLOT DATE = 5/23/2007
FILE NAME = BFILES9
PLOT SCALE = BSCALE9
USER NAME = GFOURF

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.I. 94 (I-94)

SCALE: DATE MAY 2007 DRAWN BY DCS CHECKED BY

Edens I 94 Resurfacing Project