

Northbound Edens 62636																	
Patch Locations																	
Patch Nbr	Station	Mile Marker	LN #	Revised Length (LF)	Area (SY)	Lane 1			Lane 2			Lane 3			Saw Cut (LF)	Pvmt. Reif (SY)	Tie Bar (EA)
						Ty II	Ty III	Ty IV	Ty II	Ty III	Ty IV	Ty II	Ty III	Ty IV			
38	504+63	Tower Rd	3	10	13.3	0.0	0.0	0.0	0.0	0.0	0.0	13.3	0.0	0.0	68.0	13.3	0
39	505+25	31/83	1	6	8.0	8.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
40	505+82	31/83	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
41	512+87	31/67	2	40	53.3	0.0	0.0	0.0	0.0	0.0	53.3	0.0	0.0	0.0	128.0	53.3	40
42	538+94	31/18	2	50	66.7	0.0	0.0	0.0	0.0	0.0	66.7	0.0	0.0	0.0	148.0	66.7	50
43	539+09	31/20	2	12	16.0	0.0	0.0	0.0	0.0	16.0	0.0	0.0	0.0	0.0	72.0	16.0	0
44	539+62	31/19	2	20	26.7	0.0	0.0	0.0	0.0	0.0	26.7	0.0	0.0	0.0	88.0	26.7	20
45	540+00	31/16	2	8	10.7	0.0	0.0	0.0	10.7	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
46	555+46	30/89	2	6	8.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
47	573+20	30/57	2	60	80.0	0.0	0.0	0.0	0.0	0.0	80.0	0.0	0.0	0.0	168.0	80.0	60
48	575+10	30/50	1	6	8.0	8.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
49	576+60	30/46	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
50	581+86	30/39	2	20	26.7	0.0	0.0	0.0	0.0	0.0	26.7	0.0	0.0	0.0	88.0	26.7	20
51	583+70	30/23	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
52	584+50	30/34	2	25	33.3	0.0	0.0	0.0	0.0	0.0	33.3	0.0	0.0	0.0	98.0	33.3	25
53	589+91	Dundee Rd	3	10	13.3	0.0	0.0	0.0	0.0	0.0	0.0	13.3	0.0	0.0	68.0	13.3	0
54	589+91	bridge	2	140	186.7	0.0	0.0	0.0	0.0	0.0	186.7	0.0	0.0	0.0	328.0	186.7	140
55	602+10		2	18	24.0	0.0	0.0	0.0	0.0	24.0	0.0	0.0	0.0	0.0	84.0	24.0	0
56	618+50		2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
57	619+50	LP RA8	1	25	33.3	0.0	0.0	33.3	0.0	0.0	0.0	0.0	0.0	0.0	98.0	33.3	13
	622+70	Tollway Spur															
	650+62	Lake-Cook Rd															
62636 NB Mainline Patch Totals					2660.0	69.3	0.0	420.0	178.7	84.0	1386.7	34.7	0.0	486.7	6726.0	2660.0	1380.0

Southbound Edens 62636																	
Patch Locations																	
Patch Nbr	Station	Mile Marker	LN #	Revised Length (LF)	Area (SY)	Lane 1			Lane 2			Lane 3			Saw Cut (LF)	Pvmt. Reif (SY)	Tie Bar (EA)
						Ty II	Ty III	Ty IV	Ty II	Ty III	Ty IV	Ty II	Ty III	Ty IV			
	444+54	Willow Rd															
40	431+38	33/24	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
41	423+60	33/37	3	10	13.3	0.0	0.0	0.0	0.0	0.0	0.0	13.3	0.0	0.0	68.0	13.3	0
42	416+06	33/53	3	6	8.0	0.0	0.0	0.0	0.0	0.0	0.0	8.0	0.0	0.0	60.0	8.0	0
43	415+50	33/53	1	6	8.0	8.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
	414+80	Winnetka Rd															
44	408+70	33/62	2	8	10.7	0.0	0.0	0.0	10.7	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
	394+08	Skokie River North Branch															
	378+90	Skokie Blvd / Illinois Rd															
	359+37	Lake Ave															
45	347+75	34/79	2	25	33.3	0.0	0.0	0.0	0.0	0.0	33.3	0.0	0.0	0.0	98.0	33.3	25
46	345+75	34/83	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
47	340+70	34/88	2	40	53.3	0.0	0.0	0.0	0.0	0.0	53.3	0.0	0.0	0.0	128.0	53.3	40
48	336+75	34/92	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
49	329+90	35/15	3	8	10.7	0.0	0.0	0.0	0.0	0.0	0.0	10.7	0.0	0.0	64.0	10.7	0
50	327+40	35/20	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
	318+71	Glenview Rd															
51	316+80	35/39	2	15	20.0	0.0	0.0	0.0	0.0	20.0	0.0	0.0	0.0	0.0	78.0	20.0	0
52	297+00	35/77	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
	296+23	Old Orchard															
62636 SB Mainline Patch Totals					996.0	130.7	24.0	173.3	157.3	72.0	126.7	114.7	44.0	153.3	3990.0	996.0	217.5

	Area (SY)	Lane 1			Lane 2			Lane 3			Saw Cut (LF)	Pvmt. Reif (SY)	Tie Bar (EA)
		Ty II	Ty III	Ty IV	Ty II	Ty III	Ty IV	Ty II	Ty III	Ty IV			
62636 Mainline Patch Totals	3656.0	200.0	24.0	593.3	336.0	156.0	1513.3	149.3	44.0	640.0	10716.0	3656.0	1597.5

PLOT DATE: 5/22/07
 PLOT SCALE: 1"=50'
 USER: MMS

REVISIONS				
NAME	DATE			
SCALE:		DATE: MAY 2007		
DRAWN BY:		CHECKED BY:		