CONTRACT #62719

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	3034 N-1	COOK	71	5
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	HSIP CONSTRUCTION TYPE CODE: I000-2A 90% FED. 10% STATE	Y031-IF TRAFFIC 90% FED. 5% STATE 5% CITY		F CONSTRUCTION TYPE CODE: Y030-IE LIGHTING 80% FED. (STP-U) 20% CITY		
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1				
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	566		566				
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1204		1204				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	722		722				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1368		1368				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2317		2317				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	113		113				
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2				
87700140	STEEL MAST ARM ASSEMBLY AND POLE, 20 FT.	EACH	1		1				
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1		1				
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	2		2				
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8		8				
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4		4				
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	60		60				
87900200	DRILL EXISTING HANDHOLE	EACH	1		1				
88000200	SIGNAL HEAD, 1-FACE, 3-SECTION, WITH ONE DUAL-INDICATION SECTION, MAST ARM MOUNTED	EACH	4		4				
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	8		8				
88500100	INDUCTIVE LOOP DETECTOR	EACH	10		10				
88600100	DETECTOR LOOP, TYPE I	FOOT	713		713				
88800100	PEDESTRIAN PUSH-BUTTON	EACH	4		4				
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1				
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1				

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	HSIP CONSTRUCTION TYPE CODE: I000-2A 90% FED. 10% STATE	Y031-IF TRAFFIC 90% FED. 5% STATE 5% CITY		F CONSTRUCTION TYPE CODE: Y030-IE LIGHTING 80% FED. (STP-U) 20% CITY		
89502380	REMOVE EXISTING HANDHOLE	EACH	6		6				
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		9				
A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	4	4					
A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	8	8					
A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	8	8					
A2012001	TREE, AESCULUS X CARNE BRIOTTI (BRIOTTI HORSECHESTNUT), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5					
~~B2003114~~	~~TREE, MALUS CORALBURST (CORALBURST CRAB APPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED~~	~~EACH~~	~~5~~	~~5~~					
~~B2003116~~	~~TREE, MALUS CORALBURST (CORALBURST CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED~~	~~EACH~~	~~2~~	~~2~~					
K1005863	TREE ROOT PRUNING	EACH	5	5					
X0301407	PERENNIAL PLANTS, GALLON POT	UNIT	1	1					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103					
~~X0322453~~	~~WEED CONTROL, PRE-EMERGENT~~	~~POUND~~	~~100~~	~~100~~					
X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	100	100					
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1447		1447				
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	42	42					
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	13	13					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	550	550					
X6020095	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2					
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1				
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	1473		1473				
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	637		637				
88030020	SIGNAL HEAD ,LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4		4				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
127TH ST. AT MAPLE AVE.

PLOT DATE: 1/9/2007

1/9/2007
pdarotes$dgn004039pn.rdwy.dgn

1-11-07

5