

SUMMARY OF QUANTITIES

URBAN
 90% FED. / 10% STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	NB ROADWAY 1000	SB ROADWAY 1000	DRAINAGE 1000	BRIDGES X231-2A	BRIDGES X031-2A	BRIDGES X131-2A
55021600	RECP CL III, TYP 2, REIN. CONC. CULVERT, ST. DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	80			80			
59000200	EPoxy CRACK INJECTION	FOOT	500				300	100	100
60208240	CATCH BASINS, TYPE C. TYPE 24 FRAME AND GRATE	EACH	8			8			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	757			757			
63500105	DELINEATORS	EACH	2385	1183	1202				
64200105	SHOULDER RUMBLE STRIP	FOOT	135,522	67,872	67,650				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	20	10	10				
67100100	MOBILIZATION	L SUM	1	0.4	0.4		0.2		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	16,000	8,000	8,000				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,700	850	850				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4,600	2,300	2,300				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	174,596	86,159	88,437				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	27,060	13,732	13,328				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	6,112	3,132	2,980				
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	37,108	18,554	18,554				
* 78008210	POLYUREA PAVEMENT MARKING, TYPE I, 4"	FOOT	5002	2501	2501				
* 78008220	POLYUREA PAVEMENT MARKING, TYPE I, 5"	FOOT	1,252	626	626				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3,710	1,855	1,855				
* 78200510	BARRIER WALL MARKERS, TYPE A	EACH	978	489	489				
78300100	PAVEMENT MARKING REMOVAL	SO FT	99,220	49,610	49,610				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3,710	1,855	1,855				
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,000	1000					
X0321743	SILICONE JOINT SEALER, 1"	FOOT	107				107		
X0321744	SILICONE JOINT SEALER, 2"	FOOT	1,343				613	260	470
* X0322247	MAINTENANCE OF EXISTING TRAFFIC SURVEILLANCE	L SUM	1	0.5	0.5				
* X0322300	ELECTRIC CABLE IN CONDUIT NO.18 4/C, TWISTED, SHIELDED	FOOT	10,133	10,133					
X0322729	MATERIAL TRANSFER DEVICE	TON	37,284	18,672	18,612				
X0322905	PRECAST PRESTRESSED CONCRETE I-BEAM REPAIRS	L. SUM	1						
X0325114	ADJUSTING DRAINAGE SCUPPERS, TYPE A	EACH	14				6	7	1
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	7					7	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	1300				100	100	100
X0325428	CLASS A PATCHES, TYPE II, 10 INCH (SPECIAL)	SQ YD	310						

* - SPECIALTY ITEMS

PLOT DATE = 5/23/2007
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 USER NAME = #FOUNT#

Rev. 7-20-07

REV.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 F.A.I. 94 (I-94)

SCALE: DATE MAY 2007 DRAWN BY DCS CHECKED BY