

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 94	2006-043 RS	COOK	135	98
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		

Contract # 62747

TOTAL BILL OF MATERIAL

Item	Unit	Super.	Sub.	Total
Concrete Removal	Cu. Yd.	63.8		63.8
Protective Shield	Sq. Yd.	4,208		4,208
Concrete Superstructure	Cu. Yd.	71.8		71.8
Bridge Deck Grooving	Sq. Yd.	5,951		5,951
Protective Coat	Sq. Yd.	156		156
Reinforcement Bars, Epoxy Coated	Pound	6,910		6,910
Bar Splicers	Each	68		68
Preformed Joint Strip Seal	Foot	154		154
<hr/>				
Bridge Deck Microsilica Concrete Overlay, 2 1/2"	Sq. Yd.	6,059		6,059
Bridge Deck Hydro-Scarification, 1/2"	Sq. Yd.	6,059		6,059
Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	31		31
Deck Slab Repair (Full Depth, Type II)	Sq. Yd.	279		279
Modular Expansion Joint - Swivel, 6"	Foot	152		152
Silicone Bridge Joint Sealer, 2"	Foot	470		470
* Adjusting Drainage Scuppers, Type A	Each	1		1

\* Requires Special Provision

INDEX OF SHEETS

- 96 GENERAL PLAN & ELEVATION
- 97 STRUCTURAL NOTES
- 98 TOTAL BILL OF MATERIAL AND INDEX OF SHEETS
- 99 TYPICAL SECTION THRU BRIDGE
- 100 CONSTRUCTION STAGING DETAILS
- 101 NORTH EXPANSION JOINT REMOVAL & REPLACEMENT PLAN
- 102 NORTH EXPANSION JOINT REMOVAL & REPLACEMENT DETAILS
- 103 SOUTH EXPANSION JOINT REMOVAL & REPLACEMENT PLAN
- 104 SOUTH EXPANSION JOINT REMOVAL & REPLACEMENT DETAILS
- 104a REINFORCING BAR DETAILS & SUPERSTRUCTURE BILL OF MATERIAL
- 104b EXPANSION JOINT DETAILS
- 104c TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION
- 104d DRAINAGE SCUPPER ADJUSTMENT DETAILS
- 104e SCARIFICATION AND OVERLAY DETAILS
- 104f BAR SPLICER ASSEMBLY DETAILS

T:\2298\struct\dgn\0103TOT00.dgn

DESIGNED -	JSD
CHECKED -	DWH
DRAWN -	EF
CHECKED -	DWH

**LOCHNER**  
H.W. LOCHNER, INC., CHICAGO, ILLINOIS

TOTAL BILL OF MATERIAL  
AND INDEX OF SHEETS  
F.A.I. 94/ (EDENS EXPRESSWAY)  
OVER U.P.R.R.  
COOK COUNTY  
STATION 277+05.05  
STRUCTURE NO. 016-0103 & 016-0104