

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 94	2006-043 RS	COOK	135	118b
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		

Contract # 62747

TOTAL BILL OF MATERIAL

Item	Unit	Super.	Sub.	Total
Concrete Removal	Cu. Yd.	63.7		63.7
Protective Shield	Sq. Yd.	2,443		2,443
Concrete Superstructure	Cu. Yd.	69.2		69.2
Bridge Deck Grooving	Sq. Yd.	3,105		3,105
Protective Coat	Sq. Yd.	120		120
Reinforcement Bars, Epoxy Coated	Pound	6,600		6,600
Bar Splicers	Each	64		64
Preformed Joint Strip Seal	Foot	297		297
△ Bridge Deck Microsilica Concrete Overlay, 2 1/2"	Sq. Yd.	3,145		3,145
Bridge Deck Hydro-Scarification, 1/2"	Sq. Yd.	3,145		3,145
Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	16		16
Deck Slab Repair (Full Depth, Type II)	Sq. Yd.	144		144
△ Temporary Shoring and Cribbing	Each	2		2
Silicone Bridge Joint Sealer, 2"	Foot	260		260
* Adjusting Drainage Scuppers, Type A	Each	7		7
△ Structural Repair of Concrete (Depth Greater Than 5")	Sq. Ft.		7	7

* Requires Special Provision

INDEX OF SHEETS

- 118 GENERAL PLAN & ELEVATION
- 118a STRUCTURAL NOTES
- 118b TOTAL BILL OF MATERIAL AND INDEX OF SHEETS
- 119 TYPICAL SECTION THRU BRIDGE
- 120 CONSTRUCTION STAGING DETAILS
- 121 EXPANSION JOINT REMOVAL & REPLACEMENT PLAN
- 122 EXPANSION JOINT REMOVAL & REPLACEMENT DETAILS
- 122a REINFORCING BAR DETAILS & SUPERSTRUCTURE BILL OF MATERIAL
- 122b EXPANSION JOINT DETAILS
- 122c TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION
- 122d DRAINAGE SCUPPER ADJUSTMENT DETAILS
- 122e SCARIFICATION AND OVERLAY DETAILS
- 122f BAR SPLICER ASSEMBLY DETAILS

TOTAL BILL OF MATERIAL
AND INDEX OF SHEETS
F.A.I. 94/ (EDENS EXPRESSWAY)
OVER NORTH BRANCH
COOK COUNTY
STATION 23+63.00
STRUCTURE NO. 016-0107

DESIGNED -	JSD
CHECKED -	DWH
DRAWN -	EF
CHECKED -	DWH

LOCHNER
H.W. LOCHNER, INC., CHICAGO, ILLINOIS