

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2006-043 RS	COOK	135	4

STA.	TO STA.
FED. ROAD DIST. NO. 1	ILLINOIS FED. AID PROJECT

SUMMARY OF QUANTITIES

URBAN
90% FED./10% STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	NB ROADWAY 1000	SB ROADWAY 1000	DRAINAGE 1000	BRIDGES X231-24	BRIDGES X031-24	BRIDGES X131-24
20800150	TRENCH BACKFILL	CU YD	89			89			
35102400	AGGREGATE BASE COURSE, TYPE B 12"	SQ YD	89			89			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	450	225	225				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGE WAYS	TON	100	50	50				
40600895	CONSTRUCTING TEST STRIP	EACH	4	2	2				
40600982	HOT-MIX SURFACE REMOVAL - BUTT JOINT	SQ YD	2998	1492	1546				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	2046	996	1050				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	31,357	15,636	15,721				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	21,950	10,945	11005				
44000100	PAVEMENT REMOVAL	SQ YD	89			89			
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	456	213	243				
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	56	36	20				
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	287	260	27				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	827	271	556				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	360	179	181				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	830	522	308				
44213000	PATCHING REINFORCEMENT	SQ YD	1,480	715	765				
44213200	SAW CUTS	FOOT	6,924	2,944	3,740	240			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,396	1,188	1,208				
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	89			89			
50102400	CONCRETE REMOVAL	CU YD	325.3				197.0	63.7	63.8
50157300	PROTECTIVE SHIELD	SQ YD	11,676				5,025	2,443	4,208
50300225	CONCRETE STRUCTURES	CU YD	6.0				6.0		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	358.8				217.8	69.2	71.8
50300260	BRIDGE DECK GROOVING	SQ YD	15,311				6,255	3,105	5,951
50300300	PROTECTIVE COAT	SQ YD	754				478	120	156
50500605	ADJUST AND REPOSITION BEARINGS	EACH	1				1		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	41,070				27,560	6,600	6,910
50800515	BAR SPLICERS	EACH	364				232	64	68
52000110	PREFORMED JOINT STRIP SEAL	FOOT	1,217				766	297	154
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	40				40		
54002020	EXPANSION BOLTS 3/4 INCH	EACH	460				460		

PLOT DATE = 5/23/2007
FILE NAME = #FILES#
USER NAME = #USER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.I. 94 (I-94)

SCALE: DATE MAY 2007 DRAWN BY DCS CHECKED BY

Rev.