

CONTRACT NO. 62747					
F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
94	2006-043 RS	COOK	135	6	
STA. TO STA.			FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

URBAN
90% FED. / 10% STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	NB ROADWAY 1000	SB ROADWAY 1000	DRAINAGE 1000	BRIDGES X231-24	BRIDGES X031-24	BRIDGES X131-24
X0325429	CLASS A PATCHES, TYPE III, 10 INCH (SPECIAL)	SQ YD	92	36	56				
X0325430	CLASS A PATCHES, TYPE IV, 10 INCH (SPECIAL)	SQ YD	280	47	233				
* X0325815	REMOVE EXISTING CABLE	FOOT	10,133	10,133					
* X0325816	CONDUIT IN TRENCH, P-DUCT, 1 1/4"	FOOT	1,000	1,000					
		EACH							
		EACH							
X4063000	PRELIMINARY TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	1	1				
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	37,284	18,672	18,612				
X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	30,932	15,491	15,441				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	13,021	6,521	6,500				
X5050715	JACK AND REMOVE EXISTING BEARINGS	EACH	40				40		
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.5	0.5				
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	199	100	99				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	48	24	24				
* X8850102	INDUCTION LOOP	FOOT	2,478	2,478					
Z0006110	BRIDGE DECK MICROSILICA CONCRETE OVERLAY	SQ YD	15,368				6,164	3,145	6,059
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION, 1/2"	SQ YD	15,368				6,164	3,145	6,059
Z0010900	COLD MILLING (SPECIAL)	FOOT	89,785	44,799	44,986				
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	79				32	16	31
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	713				290	144	279
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	757			757			
Z0018800	DRAINAGE SYSTEM	L. SUM	1				1		
Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	6	3	3				
Z0030360	IMPACT ATTENUATORS, RELOCATE (SEVERE USE), TEST LEVEL 3	EACH	14	7	7				
Z0031200	JACKING AND CRIBBING	EACH	2				2		
Z0034806	MODULAR EXPANSION JOINT-SWIVEL 6"	FOOT	152						152
Z0075315	TIE BARS 5/8"	EACH	318	133	185				
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	1	3				
* 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	5	2	3				

NP = NON-PARTICIPATING
* = SPECIALTY ITEMS

Plot Date = 05/22/2007
File Name = #FILE#
Plot Scale = #SCALE#
User Name = default

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.I. 94 (I-94)

SCALE: DATE JAN 2007

DRAWN BY DCS
CHECKED BY

Edens I 94 Resurfacing Project