

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2006-043 RS	COOK	135	26
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

Northbound Edens 62747

Patch Locations																	
Patch Nbr #	Station	Mile Marker	LN #	Length (LF)	Area (SY)	Lane 1			Lane 2			Lane 3			Saw Cut (LF)	Pvmt. Reif (SY)	Tie Bar (EA)
						Ty II	Ty III	Ty IV	Ty II	Ty III	Ty IV	Ty II	Ty III	Ty IV			
419+10 Wilson Ave																	
431+64 Lawrence Ave																	
80+41N / 434+26S																	
77+23 Chicago & Nwstern RR																	
1	74+38	42/74	2	6	8.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
66+47 Elston Ave																	
2	65+75	42/62	2	6	8.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
3	62+88	42/58	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
4	62+88	42/58	3	10	13.3	0.0	0.0	0.0	0.0	0.0	0.0	13.3	0.0	0.0	68.0	13.3	0
5	62+88	42/58	1	60	80.0	0.0	0.0	80.0	0.0	0.0	0.0	0.0	0.0	0.0	168.0	80.0	30
6	62+15	42/57	1	15	20.0	0.0	20.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	78.0	20.0	0
7	62+15	42/57	2	35	46.7	0.0	0.0	0.0	0.0	0.0	46.7	0.0	0.0	0.0	118.0	46.7	35
8	60+00	42/54	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
56+41 Foster Ave																	
9	55+30	42/46	3	25	33.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	33.3	98.0	33.3	13
10	49+01	42/34	1	50	66.7	0.0	0.0	66.7	0.0	0.0	0.0	0.0	0.0	0.0	148.0	66.7	25
45+87 Forest Preserve Overpass																	
29+14 Cicero Ave																	
23+63 Chicago River North Branch																	
19+29 Forest Glen																	
11	17+75	41/75	2	6	8.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
12	5+43	41/51	3	10	13.3	0.0	0.0	0.0	0.0	0.0	0.0	13.3	0.0	0.0	68.0	13.3	0
0+00N / 0+00S																	
1+75 Peterson Ave																	
13	5+80	41/30	3	6	8.0	0.0	0.0	0.0	0.0	0.0	0.0	8.0	0.0	0.0	60.0	8.0	0
14	7+20	41/28	2	6	8.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
15	11+50	41/30	2	6	8.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
27+45 Devon Ave																	
16	38+50	40/68	3	10	13.3	0.0	0.0	0.0	0.0	0.0	0.0	13.3	0.0	0.0	68.0	13.3	0
17	49+56	40/47	1	10	13.3	13.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
18	51+67	40/43	3	6	8.0	0.0	0.0	0.0	0.0	0.0	0.0	8.0	0.0	0.0	60.0	8.0	0
19	52+72	40/41	1	60	80.0	0.0	0.0	80.0	0.0	0.0	0.0	0.0	0.0	0.0	168.0	80.0	30
54+30 Pratt Ave																	
80+75 Touhy Ave																	
20	85+28	39/78	3	10	13.3	0.0	0.0	0.0	0.0	0.0	0.0	13.3	0.0	0.0	68.0	13.3	0
21	94+40	39/59	2	6	8.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
22	95+00	39/59	1	12	16.0	0.0	16.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	72.0	16.0	0
23	108+16	39/34	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
24	113+36	39/24	3	6	8.0	0.0	0.0	0.0	0.0	0.0	0.0	8.0	0.0	0.0	60.0	8.0	0

Southbound Edens 62747

Patch Locations																	
Patch Nbr #	Station	Mile Marker	LN #	Revised Length (LF)	Area (SY)	Lane 1			Lane 2			Lane 3			Saw Cut (LF)	Pvmt. Reif (SY)	Tie Bar (EA)
						Ty II	Ty III	Ty IV	Ty II	Ty III	Ty IV	Ty II	Ty III	Ty IV			
296+23 Old Orchard																	
1	293+40	35/84	3	8	10.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
2	292+00	35/87	1	10	13.3	13.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
3	291+90	35/87	3	8	10.7	0.0	0.0	0.0	0.0	0.0	0.0	10.7	0.0	0.0	64.0	10.7	0
4	290+60	35/90	1	8	10.7	10.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
5	289+80	35/92	3	6	8.0	0.0	0.0	0.0	0.0	0.0	0.0	8.0	0.0	0.0	60.0	8.0	0
6	289+00	35/94	1	8	10.7	10.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
7	283+25	36/02	1	10	13.3	13.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
8	283+25	36/02	2	6	8.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
277+05 Simpson Ave																	
9	266+10	36/36	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
265+65 Golf Rd																	
10	263+50	36/41	1	8	10.7	10.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
238+65 Church St																	
11	223+60	37/17	3	10	13.3	0.0	0.0	0.0	0.0	0.0	0.0	13.3	0.0	0.0	68.0	13.3	0
211+99 Dempster St																	
12	195+90	37/69	1	10	13.3	13.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
184+12 Lincoln Ave																	
155+24 Oakton Ave																	
149+25 Gross Point Rd																	
13	127+10	38/98	2	30	40.0	0.0	0.0	0.0	0.0	0.0	40.0	0.0	0.0	0.0	108.0	40.0	30
114+92 Niles Center Rd																	
14	110+70	39/28	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
15	109+75	39/33	2	6	8.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
16	109+50	39/33	2	8	10.7	0.0	0.0	0.0	10.7	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
17	102+50	39/45	2	8	10.7	0.0	0.0	0.0	10.7	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
18	99+25	39/33	1	8	10.7	10.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
19	99+25	39/33	2	6	8.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
20	97+50	39/58	1	8	10.7	10.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
21	86+44	39/75	1	8	10.7	10.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
22	83+65	39/80	2	8	10.7	0.0	0.0	0.0	10.7	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
80+75 Touhy Ave																	
23	80+00	39/90	2	6	8.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
24	79+50	39/91	2	8	10.7	0.0	0.0	0.0	10.7	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
25	79+50	39/91	1	8	10.7	10.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
26	74+00	39/98	2	6	8.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
27	63+50	40/21	2	8	10.7	0.0	0.0	0.0	10.7	0.0	0.0	0.0	0.0	0.0	64.0	10.7	0
28	61+50	40/23	1	6	8.0	8.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	60.0	8.0	0
29	58+50	LP DC4	1	10	13.3	13.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
30	58+50	LP DC4	2	10	13.3	0.0	0.0	0.0	13.3	0.0	0.0	0.0	0.0	0.0	68.0	13.3	0
54+30 Pratt Ave																	

ILLINOIS DEPARTMENT OF TRANSPORTATION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
MAINLINE PATCHING SCHEDULE
LAWRENCE AVENUE TO OLD ORCHARD ROAD
 SCALE: _____ DRAWN BY _____
 DATE: MAY 2007 CHECKED BY _____

Edens I 94 Resurfacing Project

PLOT DATE = 5/22/2007
 FILE NAME = #FILEL9
 PLOT SCALE = #SCALE9
 USER NAME = #DTPUT