

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 94	2006-043 RS	COOK	135	98
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

Contract # 62747

TOTAL BILL OF MATERIAL

Item	Unit	Super.	Sub.	Total
Concrete Removal	Cu. Yd.	63.8		63.8
Protective Shield	Sq. Yd.	4,208		4,208
Concrete Superstructure	Cu. Yd.	71.8		71.8
Bridge Deck Grooving	Sq. Yd.	5,951		5,951
Protective Coat	Sq. Yd.	156		156
Reinforcement Bars, Epoxy Coated	Pound	6,910		6,910
Bar Splicers	Each	68		68
Preformed Joint Strip Seal	Foot	154		154
Epoxy Crack Injection	Foot		100	100
Bridge Deck Microsilica Concrete Overlay, 2 1/2"	Sq. Yd.	6,059		6,059
Bridge Deck Hydro-Scarification, 1/2"	Sq. Yd.	6,059		6,059
Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	31		31
Deck Slab Repair (Full Depth, Type II)	Sq. Yd.	279		279
Modular Expansion Joint - Swivel, 6"	Foot	152		152
Silicone Bridge Joint Sealer, 2"	Foot	470		470
* Adjusting Drainage Scuppers, Type A	Each	1		1
Structural Repair of Concrete (Depth Equal to or Less Than 5")	Sq. Ft.		100	100

* Requires Special Provision

INDEX OF SHEETS

96	GENERAL PLAN & ELEVATION
97	STRUCTURAL NOTES
98	TOTAL BILL OF MATERIAL AND INDEX OF SHEETS
99	TYPICAL SECTION THRU BRIDGE
100	CONSTRUCTION STAGING DETAILS
101	NORTH EXPANSION JOINT REMOVAL & REPLACEMENT PLAN
102	NORTH EXPANSION JOINT REMOVAL & REPLACEMENT DETAILS
103	SOUTH EXPANSION JOINT REMOVAL & REPLACEMENT PLAN
104	SOUTH EXPANSION JOINT REMOVAL & REPLACEMENT DETAILS
104a	REINFORCING BAR DETAILS & SUPERSTRUCTURE BILL OF MATERIAL
104b	EXPANSION JOINT DETAILS
104c	TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION
104d	DRAINAGE SCUPPER ADJUSTMENT DETAILS
104e	SCARIFICATION AND OVERLAY DETAILS
104f	BAR SPLICER ASSEMBLY DETAILS

T:\2298\struct\dgn\0103T0100.dgn

DESIGNED	-	JSD
CHECKED	-	DWH
DRAWN	-	EF
CHECKED	-	DWH

LOCHNER
H.W. LOCHNER, INC., CHICAGO, ILLINOIS

TOTAL BILL OF MATERIAL
AND INDEX OF SHEETS
F.A.I. 94/ (EDENS EXPRESSWAY)
OVER U.P.R.R.
COOK COUNTY
STATION 277+05.05
STRUCTURE NO. 016-0103 & 016-0104