

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	SHEETS	SHEET NO.
F.A.I. 94	2006-043 RS	COOK	135	113b
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

Contract # 62747

TOTAL BILL OF MATERIAL

Item	Unit	Super.	Sub.	Total
Concrete Removal	Cu. Yd.	28.1		28.1
Protective Shield	Sq. Yd.	672		672
Concrete Superstructure	Cu. Yd.	31.7		31.7
Bridge Deck Grooving	Sq. Yd.	611		611
Protective Coat	Sq. Yd.	65		65
Reinforcement Bars, Epoxy Coated	Pound	5,080		5,080
Bar Splicers	Each	32		32
Preformed Joint Strip Seal	Foot	109		109
Epoxy Crack Injection	Foot		100	100
Bridge Deck Microsilica Concrete Overlay, 2 1/2"	Sq. Yd.	588		588
Bridge Deck Hydro-Scarification, 1/2"	Sq. Yd.	588		588
Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	3		3
Deck Slab Repair (Full Depth, Type II)	Sq. Yd.	29		29
Silicone Bridge Joint Sealer, 1"	Foot	107		107
Silicone Bridge Joint Sealer, 2"	Foot	134		134
* Precast Prestressed Concrete I-Beam Repairs	L. Sum	1		1
Structural Repair of Concrete (Depth Equal to or Less Than 5")	Sq. Ft.		50	50

\* Requires Special Provision

INDEX OF SHEETS

- 113 GENERAL PLAN & ELEVATION
- 113a STRUCTURAL NOTES
- 113b TOTAL BILL OF MATERIAL AND INDEX OF SHEETS
- 114 TYPICAL SECTION THRU BRIDGE
- 115 CONSTRUCTION STAGING DETAILS
- 116 EXPANSION JOINT REMOVAL & REPLACEMENT PLAN
- 117 EXPANSION JOINT REMOVAL & REPLACEMENT DETAILS
- 117a REINFORCING BAR DETAILS & SUPERSTRUCTURE BILL OF MATERIAL
- 117b EXPANSION JOINT DETAILS
- 117c TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION
- 117d SCARIFICATION AND OVERLAY DETAILS
- 117e BAR SPLICER ASSEMBLY DETAILS

I:\2298\struct\dgn\0106TOT00.dgn

DESIGNED -	JSD
CHECKED -	DWH
DRAWN -	EF
CHECKED -	DWH

**LOCHNER**  
H.W. LOCHNER, INC., CHICAGO, ILLINOIS

TOTAL BILL OF MATERIAL  
AND INDEX OF SHEETS  
F.A.I. 94/ (EDENS EXPRESSWAY)  
OVER FOREST GLEN  
COOK COUNTY  
STATION 19+28.67  
STRUCTURE NO. 016-0106