

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 94	2006-043 RS	COOK	135	118b
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

Contract # 62747

TOTAL BILL OF MATERIAL

Item	Unit	Super.	Sub.	Total
Concrete Removal	Cu. Yd.	63.7		63.7
Protective Shield	Sq. Yd.	2,443		2,443
Concrete Superstructure	Cu. Yd.	69.2		69.2
Bridge Deck Grooving	Sq. Yd.	3,105		3,105
Protective Coat	Sq. Yd.	120		120
Reinforcement Bars, Epoxy Coated	Pound	6,600		6,600
Bar Splicers	Each	64		64
Preformed Joint Strip Seal	Foot	297		297
Epoxy Crack Injection	Foot		100	100
Bridge Deck Microsilica Concrete Overlay, 2 1/2"	Sq. Yd.	3,145		3,145
Bridge Deck Hydro-Scarification, 1/2"	Sq. Yd.	3,145		3,145
Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	16		16
Deck Slab Repair (Full Depth, Type II)	Sq. Yd.	144		144
Jacking and Cribbing	Each	2		2
Silicone Bridge Joint Sealer, 2"	Foot	260		260
* Adjusting Drainage Scuppers, Type A	Each	7		7
Structural Repair of Concrete (Depth Equal to or Less Than 5")	Sq. Ft.		100	100

* Requires Special Provision

INDEX OF SHEETS

118	GENERAL PLAN & ELEVATION
118a	STRUCTURAL NOTES
118b	TOTAL BILL OF MATERIAL AND INDEX OF SHEETS
119	TYPICAL SECTION THRU BRIDGE
120	CONSTRUCTION STAGING DETAILS
121	EXPANSION JOINT REMOVAL & REPLACEMENT PLAN
122	EXPANSION JOINT REMOVAL & REPLACEMENT DETAILS
122a	REINFORCING BAR DETAILS & SUPERSTRUCTURE BILL OF MATERIAL
122b	EXPANSION JOINT DETAILS
122c	TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION
122d	DRAINAGE SCUPPER ADJUSTMENT DETAILS
122e	SCARIFICATION AND OVERLAY DETAILS
122f	BAR SPLICER ASSEMBLY DETAILS

TOTAL BILL OF MATERIAL
AND INDEX OF SHEETS
F.A.I. 94/ (EDENS EXPRESSWAY)
OVER NORTH BRANCH
COOK COUNTY
STATION 23+63.00
STRUCTURE NO. 016-0107

DESIGNED -	JSD
CHECKED -	DWH
DRAWN -	EF
CHECKED -	DWH

LOCHNER
H.W. LOCHNER, INC., CHICAGO, ILLINOIS