

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	(125BR-2)D	HENRY	34	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

44000700 APPROACH SLAB REMOVAL			
SQ YD	LOCATION		
68.5	IL 78	680 + 30.80	680 + 54.72
68.5		681 + 34.33	681 + 58.06
137	TOTAL		

20200100 EARTH EXCAVATION

CU YD	LOCATION		
235.00	IL 78	675+33.82	684+ 39.05
235.00	LT & RT		
235.00	TOTAL		

63000000 STEEL PLATE BEAM GUARDRAIL TYPE A

FOOT	LOCATION		
350.00	IL 78	676+36.24	679+ 86.23
37.50	RT	679+46.74	679+ 84.24
137.50	LT	681+67.79	683+ 42.78
525.00	TOTAL		

20400800 FURNISHED EXCAVATION

CU YD	LOCATION		
190.00	IL 78	675+33.82	684+ 39.05
190.00	LT & RT		
190.00	TOTAL		

63100087 TRAFFIC BARRIER TERMINAL TYPE 6A

EACH	LOCATION		
1	IL 78	679+86.23	680+ 31.82
1	RT	679+84.24	680+ 29.83
1	LT	681+57.98	682+ 03.56
1	RT	681+58.30	682+ 03.88
4	TOTAL		

25100630 EROSION CONTROL BLANKET

SQ YD	LOCATION		
500	IL 78	677+00	679+ 00
500	RT		
500	TOTAL		

63100167 TRAFFIC BARRIER TERMINAL TYPE I, SPECIAL (TANGENT)

EACH	LOCATION		
1	IL 78	675+86.24	676+ 36.24
1	RT	678+96.79	679+ 46.74
1	LT	682+03.56	682+ 53.56
1	RT	683+41.38	683+ 91.38
4	TOTAL		

28000300 TEMPORARY DITCH CHECK

EACH	LOCATION		
1.00	IL 78	676+00	
1.00	RT	677+00	
2.00	TOTAL		

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION		
200	IL 78	677+50	679+ 50
100	RT	678+50	679+ 50
300	TOTAL		

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION		
300	IL 78	677+24.19	680+ 25.61
125	RT	678+99.04	680+ 25.46
75	LT	681+61.78	682+ 38.28
150	RT	683+42.78	683+ 92.78
650	TOTAL		

31100300 SUB-BASE GRANULAR MATERIAL TYPE A 4"

SQ YD	LOCATION		
25	IL 78	678+56.82	679+ 06.82
25	RT		
25	TOTAL		

63500105 DELINEATORS

EACH	LOCATION		
1	IL 78	675+84.40	
1	RT	678+97.21	
1	LT	682+42.17	
1	RT	683+92.78	
4	TOTAL		

35300300 PORTLAND CEMENT CONCRETE BASE COURSE 8"

SQ YD	LOCATION		
22	IL 78	678+56.82	679+ 06.82
22	RT		
22	TOTAL		

42001400 BRIDGE APPROACH PAVEMENT (SPECIAL)			
SQ YD	LOCATION		
68.5	IL 78	680 + 30.80	680 + 54.72
68.5		681 + 34.33	681 + 58.06
137	TOTAL		

PLOT DATE = Wed May 16 11:33:35 2007
 FILE NAME = c:\p\proj\sta\2007\64D47\89287.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = dshmanbu