

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	(125BR-2)D	HENRY	34	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

70300520 PAVEMENT MARKING TAPE TYPE III, 4"

FOOT	LOCATION			
	IL 78			
343	RT	679+03.13 -	682+ 46.43	STAGE I (WHITE)
749	LT	677+34.57 -	684+ 83.50	STAGE I (WHITE)
773	RT	677+15.43 -	684+ 88.24	STAGE II (WHITE)
378	LT	679+04.59 -	682+ 82.69	STAGE II (WHITE)
<u>2,243</u>	TOTAL			

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION		
	IL 78		
4	RT	676+ 33.67 -	680+ 52.78
4	LT	679+ 47.24 -	680+ 53.26
4	LT	681+ 35.81 -	681+ 91.99
4	RT	681+ 36.39 -	683+ 42.77
<u>16</u>	TOTAL		

70300570 PAVEMENT MARKING TAPE TYPE III, 24"

FOOT	LOCATION			
	IL 78			
12	RT	676+99.85		STOP BAR, STAGE 1 (WHITE)
12	LT	685+00.33		STOP BAR, STAGE 1 (WHITE)
<u>24</u>	TOTAL			

78201000 TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION		
	IL 78		
1	RT	675+ 84.40	
1	LT	678+ 97.24	
1	RT	682+ 42.28	
1	LT	683+ 92.60	
<u>4</u>	TOTAL		

70301000 WORKZONE PAVEMENT MARKING REMOVAL

SQ. FT.	LOCATION			
	IL 78			
250	LT	677+34.57 -	684+ 83.05	STAGE I
258	RT	677+15.43 -	684+ 88.24	STAGE II
126	LT	679+04.59 -	682+ 82.67	STAGE II (WHITE)
24	RT	676+99.85 -		STOP BAR
24	LT	685+00.33 -		STOP BAR
<u>681</u>	TOTAL			

78300100 PAVEMENT MARKING REMOVAL

SQ. FT.	LOCATION			
	IL 78			
267	STA.	677+ 00 -	685+ 00	(CENTERLINE)
115	STA.	679+ 03.13 -	682+ 46.43	RT (STAGE I)
<u>382</u>	TOTAL			

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION		
	IL 78		
400	LT	679+12.69 -	683+ 12.32
<u>400</u>	TOTAL		

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION		
	IL 78		
1	LT	679+12.69	STAGE 1
1	LT	683+12.32	STAGE 1
<u>2</u>	TOTAL		

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION		
	IL 78		
400	RT	678+87.68 -	682+ 87.31
<u>400</u>	TOTAL		

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION		
	IL 78		
1	RT	678+87.68	STAGE 2
1	RT	682+87.31	STAGE 2
<u>2</u>	TOTAL		

78001110 PAINT PAVEMENT MARKING - LINE 4" (TWO COATS)

FOOT	LOCATION			
	IL 78			
500	STA.	675+ 00 -	685+ 00	(YELLOW SKIP DASH)
2000	RT STA	675+ 00 -	685+ 00	(WHITE EDGE LINE)
2000	LT STA	675+ 00 -	685+ 00	(WHITE EDGE LINE)
<u>4500</u>	TOTAL			

PLOT DATE = Wed May 16 11:53:42 2007
 FILE NAME = C:\P125BR-2\125BR-2\125BR-2.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = cshmanby