

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	(125BR-21D)	HENRY	34	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

BITUMINOUS SCHEDULE

STATION TO STATION	REMARKS	LENGTH (FT)	WIDTH (FT)	TOTAL AREA (SY)	40600625	40600982	48203020	40603310	40600990
					LEVELING BINDER (MM) N50 (TON)	HMA SURFACE REMOVAL BUTT JOINT (SQ YD)	HMA SHOULDERS, 5-3/4" (SQ YD)	HMA SURFACE COURSE MIX "C" N50 (TON)	TEMPORARY RAMP (SQ YD)
STA. 675+33.82 - 680+31.83	SHOULDER RT	498.01	11.75	573.33			573.33	72.24	
STA. 678+45.64 - 680+29.83	SHOULDER LT	184.19	11.75	168.22			168.22	21.20	
STA. 681+57.98 - 683+34.98	SHOULDER RT	177	11.75	144.11			144.11	18.16	
STA. 681+58.13 - 684+39.05	SHOULDER LT	280.92	11.75	292.22			292.22	36.82	
STA. 675+33.82 - 675+78.82	BUTT JOINT	45	26	132.00		73.00		11.09	
STA. 683+94.05 - 684+39.05	BUTT JOINT	45	26	132.00		73.00		11.09	
STA. 675+78.82 - 680+30.80	MAINLINE	451.98	35	1355.00	75.88			113.82	
STA. 681+58.06 - 683+94.05	MAINLINE	235.99	34	690.00	38.64			57.96	
STA. 680+43.72 - 680+54.57	TEMP. RAMP	11	33	40.04					40.04
STA. 681+34.33 - 681+45.33	TEMP. RAMP	11	33	40.04					40.04
TOTAL QUANTITY		1,940		3,567	115	146	1,178	342	80

PLOT DATE = Wed May 16 11:24:08 2007
 FILE NAME = I:\2007\64D47\64D47.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = cushmanby

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. DRAWN BY HORIZ. CHECKED BY DATE