

CONTRACT NO. 68469				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	146-1RS-7	PEORIA	62	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

TEMPORARY & PREFORMED PLASTIC PAVEMENT MARKING - LINE 6''

LOCATION	LENGTH	SKIP-DASH WHITE
	FT	FT
NORTHBOUND		
STA 77+45 - 55+10	2235	570
STA 54+45 - 51+80	265	70
STA 51+21 - 48+80	241	70
STA 48+20 - 46+13	207	60
STA 45+55 - 42+90	265	70
STA 42+28 - 36+30	598	150
STA 35+75 - 180+85	751	190
STA 178+26 - 180+85	259	70
STA 182+28 - 186+29	401	200
SOUTHBOUND		
STA 77+45 - 72+38	507.0	140
STA 71+98 - 61+68	1030.0	260
STA 60+88 - 58+38	250.0	70
STA 57+75 - 55+10	265.0	70
STA 54+45 - 51+80	265.0	70
STA 51+21 - 48+80	241.0	70
STA 48+20 - 46+13	207.0	60
STA 45+55 - 42+90	265.0	70
STA 42+28 - 40+07	221.0	60
STA 39+59 - 180+92	1142.0	300
STA 182+28 - 186+29	401.0	110
TOTAL		2730

TEMPORARY & THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS

LOCATION	YELLOW TURN ARROWS	
	#	SQ FT
STA 77+45 - 75+45	4	62.4
NB STA 73+60 - 72+38	2	31.2
SB STA 71+98 - 71+07	2	31.2
STA 60+88 - 58+38	2	31.2
STA 57+75 - 55+10	4	62.4
STA 54+45 - 51+80	4	62.4
STA 51+21 - 48+80	4	62.4
STA 48+20 - 46+13	4	62.4
STA 45+55 - 42+90	6	93.6
STA 42+28 - 40+07	4	62.4
STA 39+59 - 37+78	2	31.2
SB STA 35+48 - 174+95	2	31.2
SB STA 179+78 - 180+85	2	31.2
SB STA 182+28 - 184+20	3	46.8
SB STA 182+70 - 183+20	2	31.2
ADAMS STA 13+06 - 13+70	2	31.2
ADAMS STA 13+06 (COMBO)	1	26.0
TOTALS	50	790.4

MOBILIZATION	
LOCATION	LUMP SUM
PROJECT LIMITS	1
TOTAL	1

DETECTOR LOOP, TY 1	
LOCATION	FT
SB STA 70+43	80.0
TOTAL	80.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DATE: HORIZ. DRAWN BY: CHECKED BY:

PLOT DATE = 4/26/2007
 PLOT SCALE = 40.0000 / IN.
 USER NAME = conwrapj