

F.A.S. RTE. 138B	SECTION	COUNTY	TOTAL SHEET SHEETS NO.
		PEORIA	20 3
STA.	TO STA.		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT			

SUMMARY OF QUANTITIES

PEORIA (URBAN) 100% STATE SAFETY - 2A

CODE NO.	ITEM	UNIT	SN072 -0047	SN072 -0137	TOTAL
35600712	HOT MIX ASPHALT BASE COURSE WIDENING, 9"	SQ. YD.	248	290	538
44001005	HOT MIX ASPHALT SURFACE REMOVAL	SQ. YD.	27.6	14	41.6
40603335	HOT MIX ASPHALT SURFACE COURSE, MIX "D", N50	TONS	29.5	14.4	43.9
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ. YD.	248	66	314
50300255	CONCRETE SUPERSTRUCTURES	CU YD		3.7	3.7
50400305	PPC DECK BEAMS (17" DEPTH)	SQ. FT.	0	1,155	1,155
50400405	PPC DECK BEAMS (21" DEPTH)	SQ. FT.	1225	0	1225
50400505	PPC DECK BEAMS (27" DEPTH)	SQ. FT.	957	0	957
50300300	PROTECTIVE COAT	SQ YD		50	50
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	852	1,070	1,922
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND		80	80
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ. YD.	262	132.5	394.5
50900905	REMOVING & RE-ERECTING EXISTING RAILING	FOOT		1,105	1,105
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	981	456	1,437
67100100	MOBILIZATION	LSUM	0.5	0.5	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	0	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	0.5	0.5	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	LSUM	0.5	0.5	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	LSUM	0	1	1

DATE: 05-18-07
 FILE: C:\ENR\RA\T\STDA\PLANS\SDMO\1\1\BRIDGE Rep\Contract\68751\072-0137\SUM72-0137L\Drawn\Bighill\c.dwg
 SCALE: 1/8"=1'-0"
 PLOT:

REVISIONS	
NAME	DATE
CEJ	06/08/07

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE 04-20-2007
 HORIZ. DATE 04-20-2007

DRAWN BY CEJ
 CHECKED BY