CONTRACT NO. 68751

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1388	*	PEORIA	20	6
STA. VARIOUS		TO STA. VARIOUS		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

* (Z-1D-BR-1)I-1;(ZC-15D-BR)I

SCHEDULE OF QUANTITIES

MOBILIZATION

SN. 072-0137 = 0.5 EACH
SN. 072-0047 = 0.5 EACH
1.0 EACH

PAVEMENT MARKING REMOVAL

SN. 072-0137 E.O.P. TANGENT/TAPERS = 1856 SQ. FT.
SN. 072-0047 E.O.P. TANGENT/TAPERS = 444 SQ. FT.
2300 SQ. FT.

TRAFFIC CONTROL & PROTECTION (SPECIAL)

SN. 072-0137 PROJECT SITE = 1 LSUM

TRAFFIC CONTROL & PROTECTION STANDARD 701201

PROJECT SITES = 1 LSUM

TRAFFIC CONTROL & PROTECTION STANDARD 701321

SN. 072-0047 PROJECT SITE = 1 EACH

TRAFFIC CONTROL & PROTECTION STANDARD 701326

PROJECT SITES = 1 LSUM

TEMPORARY CONCRETE BARRIER

SN. 072-0137 DECK, TANGENT & TAPERS = 336 FOOT
SN. 072-0047 DECK, TANGENT & TAPERS = 408 FOOT
408 FOOT

RELOCATE TEMPORARY CONCRETE BARRIER

SN. 072-0137 DECK, TANGENT & TAPERS = 672 FOOT
SN. 072-0047 DECK, TANGENT & TAPERS = 408 FOOT
1080 FOOT

WIDTH RESTRICTION SIGNING

PROJECT SITES = 1 LSUM

BITUMINOUS CONCRETE SHOULDER REMOVAL

SN. 072-0137 WEST APPROACH CORNERS = 66 SQ. YD.
SN. 072-0047 APPROACH CORNERS = 248 SQ. YD.
314 SQ. YD.

HOT MIX ASPHALT BASE COURSE WIDENING, 9"

SN. 072-0137 WEST APPROACH CORNERS = 290 SQ. YD.
SN. 072-0047 APPROACH CORNERS = 248 SQ. YD.
538 SQ. YD.

IMPACT ATTEN., TEMP. (NRD), TEST LEV 2

SN. 072-0137 WORKZONE PROTECTION = 2 EACH
SN. 072-0047 WORKZONE PROTECTION = 2 EACH
2 EACH

IMPACT ATTEN., RELOC. (NRD), TEST LEV 2

SN. 072-0137 WORKZONE PROTECTION = 2 EACH
SN. 072-0047 WORKZONE PROTECTION = 4 EACH
6 EACH

PAVEMENT MARKING TAPE, TYPE III, 4"

SN. 072-0137 WORKZONE PROTECTION = 6936 FOOT
SN. 072-0047 WORKZONE PROTECTION = 1130 FOOT
8066 FOOT

HOT MIX ASPHALT SURFACE REMOVAL

SN. 072-0137 DECK REPLACEMENT LOCATIONS = 11.5 SQ. YD.
SN. 072-0047 DECK REPLACEMENT LOCATIONS = 27.6 SQ. YD.
39.1 SQ. YD.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.
DATE 04-20-2007
DRAWN BY CEJ
CHECKED BY

PLOT DATE : 4DATE95-18-97
FILE NAME : 4FILEN\GENADMIN\STDAPLNS\SQUAD 14\BRIDGE Rep-Corrected\68470 SN072-0137\SN072-0137LBeam-Bigholl-w-C-Ab.dgn
PLOT SCALE : 4SCALE4
PLOT SCALE : 4REF4
REFERENCE : 4REF4