

| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---------|-----------------|--------------|-----------|
| 138B | * | PEORIA | 20 | 7 |
| STA. VARIOUS | | TO STA. VARIOUS | | |
| FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT | | | | |
| • (2-1D-BR-11)-1-(2C-15D-BR)1 | | | | |

SCHEDULE OF QUANTITIES

REMOVAL OF EXISTING PPC DECK BEAMS

SN. 072-0137 DECK REPL. LOCATIONS = 726 SQ. FT.
 SN. 072-0047 DECK REPL. LOCATIONS = 2202 SQ. FT.
2928 SQ. FT.

PPC DECK BEAMS (17" DEPTH)

SN. 072-0137 DECK REPL. LOCATIONS = 717 SQ. FT.
 SN. 072-0047 DECK REPL. LOCATIONS = 0 SQ. FT.
717 SQ. FT.

PPC DECK BEAMS (21" DEPTH)

SN. 072-0137 DECK REPL. LOCATIONS = 0 SQ. FT.
 SN. 072-0047 DECK REPL. LOCATIONS = 1225 SQ. FT.
1225 SQ. FT.

PPC DECK BEAMS (27" DEPTH)

SN. 072-0137 BRIDGE DECK LOCATIONS = 0 SQ. FT.
 SN. 072-0047 BRIDGE DECK LOCATIONS = 957 SQ. FT.
957 SQ. FT.

ASBESTOS BEARING PAD REMOVAL

SN. 072-0137 PIER REPL. LOCATIONS = 7 EACH
 SN. 072-0047 PIER REPL. LOCATIONS = 8 EACH
15 EACH

FURNISHING & ERECTING STRUCTURAL STEEL

SN. 072-0137 BEAM REPLACEMENT LOCATIONS = 746 POUND
 SN. 072-0047 BEAM REPLACEMENT LOCATIONS = 852 POUND
1598 POUND

PORTLAND CEMENT MORTAR FAIRING COURSE

SN. 072-0137 BEAM REPLACEMENT LOCATIONS = 346 FOOT
 SN. 072-0047 BEAM REPLACEMENT LOCATIONS = 981 FOOT
1327 FOOT

WATERPROOFING MEMBRANE SYSTEM

SN. 072-0137 DECK REPLACEMENT BEAMS = 93.5 SQ. YD.
 SN. 072-0047 DECK REPLACEMENT BEAMS = 262 SQ. YD.
356 SQ. YD.

HOT MIX ASPHALT SURFACE COURSE, MIX'D, N50

SN. 072-0137 BRIDGE DECK LOCATIONS = 11.2 TONS
 SN. 072-0047 BRIDGE DECK LOCATIONS = 29.5 TONS
40.7 TONS

WORKZONE PAVEMENT MARKING REMOVAL

SN. 072-0137 LANE MARKING = 1460 FOOT
 SN. 072-0047 LANE MARKING = 1130 FOOT
2600 FOOT

EPOXY PAVEMENT MARKING-LINE 4"

CENTERLANE & E. O. P. REPLACEMENT = 3172 FOOT
 CENTERLANE & E. O. P. REPLACEMENT = 1330 FOOT
4502 FOOT

EPOXY PAVEMENT MARKING-LINE 12"

CENTERLANE DIAGONALS = 550 FOOT
 CENTERLANE DIAGONALS = 0 FOOT
550 FOOT

SN. 072-0047 IL.8
 over Kickapoo Crk.

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
 HORIZ.
 DATE 05-15-2007

DRAWN BY CEJ
 CHECKED BY

PLOT DATE: 05-15-07
 PLOT SCALE: 1"=50'-0"
 REFERENCE: #REF#