

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
730	*	MCLEAN	10	3
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

• D5 PATCHING 2008-2

GENERAL NOTES

NO COMMITMENTS

G.N.-100
 ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER
 AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT.
 WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-440B
 THE EXISTING TIE BARS BETWEEN THE EXISTING PAVEMENT AND EXISTING MEDIANS, GUTTERS
 AND/OR COMBINATION CURB AND GUTTERS THAT ARE FOUND SUITABLE FOR REUSE SHALL BE
 CLEANED, STRAIGHTENED AND INCORPORATED INTO THE NEW CONSTRUCTION. ANY EXISTING
 TIE BARS THAT ARE FOUND UNSUITABLE TO BE INCORPORATED INTO THE PROPOSED
 CONSTRUCTION DUE TO EXCESSIVE RUSTING OR DISTRESS SHALL BE REMOVED FLUSH WITH
 THE FACE OF THE EXISTING CONCRETE AND DISPOSED OF OUTSIDE THE LIMITS OF THE
 RIGHT-OF-WAY IN ACCORDANCE WITH ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS.

THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN THE
 VARIOUS REMOVAL PAY ITEMS AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

G.N.-442(SPL)
 THE PATCHING QUANTITIES INCLUDED IN THE CONTRACT ARE ESTIMATED QUANTITIES ONLY
 AND FINAL QUANTITIES FOR THE DIFERENT TYPES OF PATCHING MAY VARY.

G.N.-1004.01
 COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER
 COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD
 SPECIFICATIONS.

PLOT DATE : 8/15/2007
 FILE NAME : \\sawtooth\pub\70637\70637.dgn
 PLOT SCALE : 42.3051 / IN.
 USER NAME : collinsb

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		GENERAL NOTES

SCALE: VERT. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____