

SUMMARY OF QUANTITIES **URBAN**

CONSTRUCTION TYPE CODE

F.A.S. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	MCLEAN	11	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* CM PATCHING 2008-1				

SUMMARY OF QUANTITIES		UNIT	TOTAL QUANTITIES	FAI I-74				
CODE NO	ITEM			STA. 612+00 - 718+55				
				MCLEAN COUNTY				
			100 % STATE	1000				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	586.0	586.0				
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	656.0	656.0				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	5,855.0	5,855.0				
44200553	CLASS A PATCHES, TYPE II, 10"	SQ YD	172.0	172.0				
44200557	CLASS A PATCHES, TYPE III, 10"	SQ YD	48.0	48.0				
44200559	CLASS A PATCHES, TYPE IV, 10"	SQ YD	547.0	547.0				
44201765	CLASS D PATCHES, TYPE II, 10"	SQ YD	43.0	43.0				
44213000	PATCHING REINFORCEMENT	SQ YD	767.0	767.0				
44213200	SAW CUTS	FOOT	2,830.0	2,830.0				
67100100	MOBILIZATION	L SUM	1.0	1.0				
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	9.0	9.0				
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0	1.0				
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.0	1.0				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10.0	10.0				
78000200	THERMOPLASTIC PAVEMENT MARKING, LINE - 4"	FOOT	1,107.0	1,107.0				
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	6,587.0	6,587.0				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	659.0	659.0				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	494.0	494.0				
X4401705	PARTIAL DEPTH REMOVAL	SQ YD	667.0	667.0				
X4421000	PARTIAL DEPTH PATCHING	TON	122.0	122.0				
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0	28.0				
Z0075300	TIE BARS	EACH	205.0	205.0				

* NO SPECIALTY ITEMS