CONTRACT NO. 72847

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
①	②	SANGAMON	80	18
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

① FAP 666 & FAP 67
② (SP-Z)RS-4 & (107Z)RS-8

PAVEMENT PATCHING

LOCATION	SIZE	PAVEMENT PATCHING, TYPE I, 14 INCH	PAVEMENT PATCHING, TYPE II, 14 INCH	PAVEMENT PATCHING, TYPE III, 14 INCH	PAVEMENT PATCHING, TYPE IV, 14 INCH
	FT	SQ YD	SQ YD	SQ YD	SQ YD
NINTH STREET					
CONVERSE TO NORTH GRAND	6x6	4.00			
	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	6x20		13.33		
	6x15		10.00		
	6x10		6.67		
	6x20		13.33		
	6x30			20.00	
	6x50				33.33
NORTH GRAND TO RESERVIOR	8x12			19.56	
RESERVIOR TO DIVISION	6x12		8.00		
	6x12		8.00		
	6x30			20.00	
	20x12				26.67
	20x24				53.33
DIVISION TO ENTERPRISE	6x6	4.00			
	6x12		8.00		
	6x30			20.00	
ENTERPRISE TO PHILLIPS	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
PHILLIPS TO ENOS	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	6x30			20.00	
ENOS TO MILLER	6x6	4.00			
	6x10		6.67		
	10x12		13.33		
	8x12		10.67		
MILLER TO CARPENTER	6x12		8.00		
	6x20		13.33		
	6x12		8.00		
	10x12		13.33		
	6x30			20.00	
	6x40				26.67
CARPENTER TO REYNOLDS	6x12		8.00		
	6x20		13.33		
	6x15		10.00		
	6x12		8.00		
REYNOLDS TO MADISON	6x6	4.00			
	6x20		13.33		
	6x12		8.00		
	6x15		10.00		
	12x12			16.00	
	12x12			16.00	
	6x30			20.00	
	6x30			20.00	
	20x12				26.67
	20x12				26.67
MADISON TO JEFFERSON	6x6	4.00			
	6x12		8.00		
WASHINGTON TO ADAMS	6x12		8.00		
	12x12			16.00	
	12x24				32.00
ADAMS TO MONROE	6x12		8.00		
	20x12				26.67
	10x24				26.67
	SUBTOTAL	20.00	323.32	207.56	278.68

PAVEMENT PATCHING (CONT.)

LOCATION	SIZE	PAVEMENT PATCHING, TYPE I, 14 INCH	PAVEMENT PATCHING, TYPE II, 14 INCH	PAVEMENT PATCHING, TYPE III, 14 INCH	PAVEMENT PATCHING, TYPE IV, 14 INCH
	FT	SQ YD	SQ YD	SQ YD	SQ YD
MONROE TO CAPITOL	12x12			16.00	
CAPITOL TO COOK	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	12x12			16.00	
	8x24			21.33	
	12x12			16.00	
	12x24				32.00
	20x12				26.67
	24x24				64.00
	20x12				26.67
COOK TO LAWENCE	12x12			16.00	
	6x24			16.00	
LAWENCE TO CASS	12x12			16.00	
	12x12			16.00	
	6x24			16.00	
	10x24				26.67
CASS TO SOUTH GRAND	6x6	4.00			
	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	6x24			16.00	
	6x24			16.00	
	12x12			16.00	
	6x24			16.00	
	12x12			16.00	
	6x24			16.00	
	6x24			16.00	
	6x24			16.00	
	8x24			21.33	
	12x24				32.00
	12x36				48.00
	8x30				26.67
	10x36				40.00
SUBTOTAL		4.00	88.00	298.66	322.68
NINTH STREET TOTAL		24.00	411.32	506.22	601.36
ROUNDED		24	411	506	601
JEFFERSON					
9TH TO 7TH	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
7TH TO 6TH	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	6x12		8.00		
	6x20		13.33		
	6x30			20.00	
	12x40				53.33
6TH TO 5TH	6x12		8.00		
	8x36				32.00
5TH TO 4TH	6x12		8.00		
4TH TO 2ND	6x12		8.00		
	12x30				40.00
2ND TO 1ST	6x36			24.00	
	12x20				26.67
	8x36				32.00
SUBTOTAL			101.33	44.00	184.00
ROUNDED			101	44	184
PROJECT TOTAL		24	512	550	785

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

FAP 666 (I-55 BUSINESS LOOP-NINTH STREET)
FAP 67 (IL 97/IL 29-JEFFERSON STREET)

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 2/15/2007
FILE NAME = c:\projects\d655303\hbs_final\schedulesofquantities.dgn
PLOT SCALE = 42.3529 ' / IN.
USER NAME = laughlmr1

SUB