

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	101B-1	WABASH	34	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODED PAYITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	SN 093-0005 (IL 1)	
				WABASH COUNTY 80% FEDERAL / 20% STATE STP RURAL STATE FUNDS CONSTRUCTION TYPE CODE	
				I000-2A	X080-2A
20200100	EARTH EXCAVATION	CU YD	99	99	
20400800	FURNISHED EXCAVATION	CU YD	96	96	
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.25	0.25	
28000300	TEMPORARY DITCH CHECKS	EACH	3	3	
<del>28100109</del>	<del>STONE RIPRAP, CLASS A5</del>	<del>SQ YD</del>	<del>603</del>		<del>603</del>
28000400	PERIMETER EROSION BARRIER	FOOT	1380	1380	
<del>28200200</del>	<del>FILTER FABRIC</del>	<del>SQ YD</del>	<del>603</del>		<del>603</del>
35650500	BASE COURSE WIDENING 10"	SQ YD	150	150	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	165	165	
40600300	AGGREGATE (PRIME COAT)	TON	1	1	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	8	8	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	28	28	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	179	179	
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	24		24
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	89		89
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	257	257	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	9	9	
50300260	BRIDGE DECK GROOVING	SQ YD	611		611
50300300	PROTECTIVE COAT	SQ YD	611		611
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	299		299
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	4157		4157
50800205	REINFORCEMENT BARS (EPOXY COATED)	POUND	7590		7590
50800515	BAR SPLICERS	EACH	168		168
50901050	STEEL RAILING, TYPE SM	FOOT	332		332
51500100	NAME PLATES	EACH	1		1
59000200	EPOXY CRACK INJECTION	FOOT	45		45
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	400	400	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	471	471	

\* SPECIALTY ITEMS

Plot Date: 6/21/2007  
 Plot Time: 8:42:31 AM  
 Plotted By: kolden@sch  
 Pen Table: 1301.tbl  
 Plotment: it:0005\csc\Downscope\Baracas-Const\Instron\_Plan\03\_Summary.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**  
SHEET 1 OF 2

SCALE: VERT. N/A  
 HORIZ. N/A  
 DATE 06/20/07

DRAWN BY KMO  
 CHECKED BY SSM

Rev.