

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	101B-1	WABASH	34	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODED PAYITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	SN 093-0005 (IL 1)	
				WABASH COUNTY	
				80% FEDERAL / 20% STATE STP RURAL STATE FUNDS CONSTRUCTION TYPE CODE	
				I000-2A	X080-2A
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	778	778	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	575	575	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	550	550	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1934	1934	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	242	242	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	18	18	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	694	694	
X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNIT	SQ FT	299		299
52000110	PREFORMED JOINT STRIP SEAL	FOOT	33		33
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	7		7
X5030305	CONCRETE WEARING SURFACE 5"	SQ YD	013		013
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	22		22

*SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET 2 OF 2

SCALE: VERT. N/A
HORIZ. N/A
DATE 06/20/07

DRAWN BY KMO
CHECKED BY SSM

Plot Date: 6/25/2007
Plot Time: 10:41:11 AM
Plot By: Koderborgh
File Name: \\080055\oad\Downscope\Boroad-Construction\Plan\03_Summary.dgn