

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	101B-1	WABASH	34	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

**GUARDRAIL**

LOCATION	SIDE	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 6A	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED
STATION TO STATION		FOOT	FOOT	EACH	EACH	EACH	EACH
SN 093-0005 ( IL 1) BONPAS CREEK							
STA 146+22.46 TO STA 148+47.00	LT	114	100	1	1	4	1
STA 146+34.96 TO STA 148+47.00	RT	112	100	1	1	4	1
STA 150+13.00 TO STA 152+94.25	LT	119	100	1	1	5	1
STA 150+13.00 TO STA 152+06.75	RT	126	100	1	1	5	1
SUBTOTAL		471	400	4	4	18	4

**REMOVAL ITEMS**

LOCATION	CONCRETE REMOVAL
STATION TO STATION	CU YD
SN 093-0005 ( IL 1) BONPAS CREEK	
STA 148+46.92 TO STA 148+66.84	4.5
STA 149+93.16 TO STA 150+13.08	4.5
TOTAL	
	9

**EROSION CONTROL**

LOCATION	SIDE	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER
STATION TO STATION		EACH	FOOT
SN 093-0005 ( IL 1) BONPAS CREEK			
STA 146+00.00 TO STA 153+13.54	LT		688
STA 145+15.97 TO STA 152+30.00	RT		692
STA 148+25.00	LT	1	
STA 148+25.00	RT	1	
STA 150+25.00	LT	1	
TOTAL		3	1380

**EARTHWORK**

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	SHRINKAGE FACTOR	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STATION TO STATION	CU YD	CU YD		CU YD	CU YD
SN 093-0005 ( IL 1) BONPAS CREEK					
STA 145+20.00 TO STA 153+00.00	99	74	25	209	-135
SUBTOTAL		99	74	209	-135

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**  
SHEET 2 OF 2

SCALE: VERT. NONE  
HORIZ. NONE  
DATE 06/20/07

DRAWN BY KMO  
CHECKED BY SSM