

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
:	:	WABSON	7	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
:		EAU 9251...EAS 1848...EAU 9288		
:		2185-2...28...2985-2		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000-2A 100% STATE		
20400800	FURNISHED EXCAVATION	CU YD	7	7		
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	46.4	46.4		
40600300	AGGREGATE (PRIME COAT)	TON	223	223		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3116	3116		
40600990	TEMPORARY RAMP	SQ YD	675	675		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6232	6232		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3		
40800030	AGGREGATE (PRIME COAT)	TON	1.5	1.5		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	68.3	68.3		
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	88353	88353		
44200994	CLASS B PATCHES, TYPE II, 12 INCH	SQ YD	341	341		
44213200	SAW CUTS	FOOT	2023	2023		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	60466	60466		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5460	5460		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1699	1699		
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3		
63200310	GUARDRAIL REMOVAL	FOOT	75	75		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000-2A 100% STATE		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19404	19404		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	296	296		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	71148	71148		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	856	856		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	92	92		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6468	6468		
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	296	296		
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	71148	71148		
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	856	856		
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	92	92		
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	510	510		
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	12		
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	510	510		
*80300100	LOCATING UNDERGROUND CABLE	FOOT	50	50		
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	144	144		
Z0017202	DOWEL BARS 1 1/2"	EACH	816	816		

*SPECIALTY ITEMS