CONTRACT NO. 76897

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
793	112BR-2	BOND	52	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE X080-2A		
35600717	HOT-MIX ASPHALT BASE COURSE WIDENING, 10 1/4"	SQ YD	262	262		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	244	244		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	336	336		
20200100	EARTH EXCAVATION	CU YD	350	350		
20200500	EARTH EXCAVATION (WIDENING)	CU YD	50	50		
20300100	CHANNEL EXCAVATION	CU YD	690	690		
20400800	FURNISHED EXCAVATION	CU YD	4100	4100		
25000200	SEEDING, CLASS 2	ACRE	1	1		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90		
25100115	MULCH, METHOD 2	ACRE	1	1		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300	300		
28000300	TEMPORARY DITCH CHECKS	EACH	2	2		
28000400	PERIMETER EROSION BARRIER	FOOT	820	820		
28100109	STONE RIPRAP, CLASS A5	SQ YD	3500	3500		
28200200	FILTER FABRIC	SQ YD	3500	3500		
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	11	11		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2		
40600300	AGGREGATE (PRIME COAT)	TON	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	213	213		
40600990	TEMPORARY RAMP	SQ YD	72	72		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	54	54		
42001300	PROTECTIVE COAT	SQ YD	753	753		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	13	13		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1		
50105220	PIPE CULVERT REMOVAL	FOOT	40	40		
50300260	BRIDGE DECK GROOVING	SQ YD	705	705		
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	6769	6769		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9450	9450		
50800515	BAR SPLICERS	EACH	207	207		
50901050	STEEL RAILING, TYPE SM	FOOT	413	413		
51500100	NAME PLATES	EACH	1	1		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	66	66		
542D1063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	70	70		
542D1915	PIPE CULVERTS, CLASS D, TYPE 3 30"	FOOT	60	60		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	212.5	212.5		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE X080-2A		
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	5	5		
63200310	GUARDRAIL REMOVAL	FOOT	580	580		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	11	11		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	15	15		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1		
70106600	TEMPORARY BRIDGE TRAFFIC SIGNALS (STATE FURNISHED CONTROLLER)	EACH	1	1		
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	72	72		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1919	1919		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	800	800		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	664	664		
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	410	410		
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	390	390		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1455	1455		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	464	464		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	2		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2		
* 78100300	REPLACEMENT REFLECTOR	EACH	6	6		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	12		
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	6	6		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	5	5		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	554	554		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10		
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	82	82		
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	753	753		
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	2	2		

* SPECIALTY ITEMS

Rev.

PLOT DATE = 5/1/2007
FILE NAME = c:\projects\ed83785\plan\pln83785ed.dgn
PLOT SCALE = 49.9999 ' / IN.
REFERENCE = REF