

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	95-15,611	WASHINGTON	11	3
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000 100% STATE	---	---
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.1	5.1		
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SQ YD	5	5		
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	199	199		
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	501	501		
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ YD	574	574		
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	858	858		
44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	270	270		
44200581	CLASS A PATCHES, TYPE III, 12 INCH	SQ YD	107	107		
44200583	CLASS A PATCHES, TYPE IV, 12 INCH	SQ YD	5057	5057		
44213000	PATCHING REINFORCEMENT	SQ YD	7571	7571		
44213200	SAW CUTS	FOOT	16519	16519		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4		
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1		
70101805	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	EACH	4	4		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2148	2148		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	716	716		
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	38743	38743		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	554	554		
X4422032	PARTIAL DEPTH REMOVAL 3 1/2"	SQ YD	16815	16815		
X4421000	PARTIAL DEPTH PATCHING	TON	3295.7	3295.7		
Z0075310	TIE BARS 3/4"	EACH	2522	2522		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		---	---	---

* SPECIALTY ITEMS

PLOT DATE : 5/14/2007
 FILE NAME : c:\projects\11001187\plottables\11001187.dgn
 PLOTTER : HP DesignJet 800C / IN
 REFERENCE : AREA 2