

FIG. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	95-15,61	WASHINGTON	11	7
STA. _____		TO STA. _____		
CONTRACT NO.: 76A38				

CLASS A PAVEMENT PATCHING SCHEDULE

BEGIN LOCATION STATION	DRIVING LANE LENGTH (FT.)	PASSING LANE LENGTH (FT.)	LANE WIDTH (FT.)	TYPE II 12" PATCH (SQ. YD.)	TYPE III 12" PATCH (SQ. YD.)	TYPE IV 12" PATCH (SQ. YD.)	PATCHING REINFORCEMENT (SQ. YD.)	TIE BARS (EACH)	SAW CUTS (FT.)
EASTBOUND									
MAINLINE									
2976+00	20		6	13	0	0	13		58
3020+85	80		6	0	0	53	53	39	178
3069+85	10		12	13	0	0	13		56
3226+75	60		6	0	0	40	40	29	138
3386+76	20		6	13	0	0	13		58
3548+91	10		12	13	0	0	13		56
3721+16	80		12	0	0	107	107	39	196
3904+16	150		12	0	0	200	200	74	336
4114+81	50		12	0	0	67	67	24	136
4330+91	60		12	0	0	80	80	29	156
4586+81	50		12	0	0	67	67	24	136
4872+61	150		12	0	0	200	200	74	336
5172+58	80		12	0	0	107	107	39	196
5490+58	160		12	0	0	213	213	79	356
5811+88	40		12	0	0	53	53	19	116
6140+83	50		12	0	0	67	67	24	136
6473+94	120		12	0	0	160	160	59	276
6808+99	100		12	0	0	133	133	49	236
7148+98	40		12	0	0	53	53	19	116
7491+02	60		12	0	0	80	80	29	156
7848+52	150		12	0	0	200	200	74	336
8209+82	60		12	0	0	80	80	29	156
8580+26	150		12	0	0	200	200	74	336
8953+37	80		12	0	0	107	107	39	196
9330+79	40		12	0	0	53	53	19	116
9710+79	90		12	0	0	120	120	44	216
10092+34	90		12	0	0	120	120	44	216
10474+49	100		12	0	0	133	133	49	236
10858+44	6		12	8	0	0	8		48
11243+29	60		12	0	0	80	80	29	156
11628+53	30		12	0	0	40	40	14	96
12016+60	80		12	0	0	107	107	39	196
12407+51	100		6	0	0	67	67	49	218
12806+26	50		12	0	0	67	67	24	136
13206+87	100		12	0	0	133	133	49	236
13608+56	40		6	0	0	27	27	19	98
14011+80	100		12	0	0	133	133	49	236
14434+71	15		6	10	0	0	10		48
15% ANTICIPATED FAILURE				11	0	502	513	194	1006
TOTAL				81	0	3849	3930	1487	7709.6

Conversion Factors

Bituminous Material (Prime Coat) : 0.0003129 TONS / SQ YD
Aggregate (Prime Coat) : 0.0015 TONS / SQ YD

REVISIONS	
NAME	DATE

DRAWN BY:

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

FAI ROUTE 64
SECTION 95-(5,6)I
WASHINGTON COUNTY

#00129
#0015
#0003129
#0015
#0015
#0015