

CLASS A PAVEMENT PATCHING

BEGIN STATION	RAMP LANE	PASSING LANE	RAMP LANE	TYPE I	TYPE II	TYPE III	TYPE IV	PATCHING	TIE BARS	SAW CUTS
LOCATION	LENGTH	LENGTH	WIDTH	8" PATCH	8" PATCH	8" PATCH	8" PATCH	REINF	(EACH)	(FT.)
	(FT.)	(FT.)	(FT.)	(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(SQ. YD.)		
U.S RAMP 51										
EXIT RAMP 3 (S.W.)										
305+05	6		16	0	11	0	0	11		60
306+04	6		16	0	11	0	0	11		60
307+04	10		16	0	0	18	0	18		68
307+99	14		16	0	0	25	0	25		76
309+00	14		16	0	0	25	0	25		76
309+99	14		16	0	0	25	0	25		76
311+00	14		16	0	0	25	0	25		76
311+67	30		8	0	0	0	27	27	14	84
312+87	14		16	0	0	25	0	25		76
ENTR RAMP 4 (S.E.)										
6+15	50		16	0	0	0	89	89	24	148
6+92	60		16	0	0	0	107	107	29	168
6+94	14		16	0	0	25	0	25		76
7+84	14		16	0	0	25	0	25		76
8+83	14		16	0	0	25	0	25		76
9+84	14		16	0	0	25	0	25		76
10+81	50		16	0	0	0	89	89	24	148
11+32	14		16	0	0	25	0	25		76
11+83	14		16	0	0	25	0	25		76
EXIT RAMP 2 (N.E.)										
207+08.2	14		16	0	0	25	0	25		76
208+03.2	6		16	0	11	0	0	11		60
208+90.2	6		16	0	11	0	0	11		60
209+99.2	15		16	0	0	0	27	27		78
210+60.2	14		16	0	0	25	0	25		76
211+00.20	14		16	0	0	25	0	25		76
211+21.2	10		16	0	0	18	0	18		68
211+45.2	14		16	0	0	25	0	25		76
ENTR RAMP 1 (N.W.)										
3+16	81		8	0	0	0	72	72	40	186
3+76	14		16	0	0	25	0	25		76
4+07	8		16	0	14	0	0	14		64
4+42	40		8	0	0	0	36	36	19	104
4+70	8		16	0	14	0	0	14		64
5+71	8		16	0	14	0	0	14		64
6+61	8		16	0	14	0	0	14		64
7+17	8		16	0	14	0	0	14		64
7+77	8		16	0	14	0	0	14		64
8+43	8		16	0	14	0	0	14		64
8+72	8		16	0	14	0	0	14		64
8+81	4		8	4	0	0	0	4		32
9+10	7		8	0	6	0	0	6		38
9+57	58		8	0	0	0	52	52	28	140
9+63	6		16	0	11	0	0	11		60
15% ANTICIPATED FAILURE				1	26	65	75	166	27	494
TOTAL				5	199.00	501.00	574.00	1279.00	205.00	3783.50

Conversion Factors Bituminous Material (Prime Coat) : 0.0003129 TONS / SQ YD
Aggregate (Prime Coat) : 0.0015 TONS / SQ YD

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

FAI ROUTE 64
SECTION 95-(5,6)I
WASHINGTON COUNTY

DRAWN BY: _____

*DATE**
*DATE-TIME**
*REF**
*REF**