



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 27, 2007

SUBJECT: FAU Route 3597
(Park Avenue)
Project M-8003(815)
Section 07-00119-00-RS (Homewood)
Cook County
Contract No 83928
Item 005 A
August 3, 2007 Letting

TO PROSPECTIVE BIDDERS:

To clarify information it is necessary to revise the following:

Proposal – Revised page 6 of the Special Provisions. Revised pages 2 and 3 of the Schedule of Prices

Plan- Revised the Summary of Quantities on sheet 2.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Since the proposal sheets are printed back to back, bidders are cautioned to exercise care when inserting revised and/or added special provisions into their proposals.

Please call 217-782-7806 if any of the above-described material is not included in this transmittal.

Very truly yours,

Eric Harm
Interim Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by "P.E." in a smaller font.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

This work shall be done in accordance with Section 602 of the Standard Specifications. This item shall include all structures within the pavement. Adjustments shall be made with precast concrete adjusting rings. **No metal rings** shall be used. The rings and frames shall be set on two concentric rings of Con-Seal or Press-Seal "tar rope". Mastic shall be applied with a trowel on the outside of the rings, while the inside shall be painted with a fine cement grout. The Contractor shall take due care when adjusting sanitary frames with an existing chimney seal. The removal and replacement of the chimney seal shall be incidental to this item.

Adjustments will include the removal of the existing frame and lid, steel plate installation, backfilling before milling and adjusting a new type-1 frame w/ open lid to final elevation after milling. (See plan details.)

This work shall be paid for at the contract unit price per each for **MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID**, which shall include all labor, material, and equipment to perform the work herein specified.

MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID:

This work shall be done in accordance with Section 602 of the Standard Specifications. This item shall include all structures within the pavement. Adjustments shall be made with precast concrete adjusting rings. **No metal rings** shall be used. The rings and frames shall be set on two concentric rings of Con-Seal or Press-Seal "tar rope". Mastic shall be applied with a trowel on the outside of the rings, while the inside shall be painted with a fine cement grout. The Contractor shall take due care when adjusting sanitary frames with an existing chimney seal. The removal and replacement of the chimney seal shall be incidental to this item.

Adjustments will include the removal of the existing frame and lid, steel plate installation, backfilling before milling and adjusting a new type-1 frame w/ closed lid to final elevation after milling. (See plan details.)

This work shall be paid for at the contract unit price per each for **MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID**, which shall include all labor, material, and equipment to perform the work herein specified.

TRAFFIC CONTROL PLAN

Effective: September 30, 1985

Revised: January 1, 2007

Traffic control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual of Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

FAU 3597
07-00119-00-RS
COOK

(HOMWOOD)

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - 83928

ECMS002 DTGECM03 ECMR003 PAGE 2
RUN DATE - 07/26/07
RUN TIME - 183256

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
42400800	DETECTABLE WARNINGS	SQ FT	25.000 X				
44000157	HMA SURF REM 2	SQ YD	10,004.000 X				
44001700	COMB C C&G REM & REPL	FOOT	441.000 X				
44201711	CL D PATCH T4 5	SQ YD	78.000 X				
44201747	CL D PATCH T4 8	SQ YD	236.000 X				
44300300	AREA REF CR CON TR A	SQ YD	10,241.000 X				
48100500	AGGREGATE SHLDS A 6	SQ YD	376.000 X				
60255700	MAN ADJ NEW T1F OL	EACH	5.000 X				
60255800	MAN ADJ NEW T1F CL	EACH	12.000 X				
60263010	INL RECON NEW T2F&G	EACH	7.000 X				
60266600	VALVE BOX ADJ	EACH	6.000 X				
67100100	MOBILIZATION	L SUM	1.000 X				
70102620	TR CONT & PROT 701501	L SUM	1.000 X				
70102640	TR CONT & PROT 701801	L SUM	1.000 X				
70300100	SHORT-TERM PAVT MKING	FOOT	7,500.000 X				

* removed pay item 60300310

revised 7/27/07

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
78001110	PAINT PVT MK LINE 4	FOOT	11,492.000 X		=		
78001130	PAINT PVT MK LINE 6	FOOT	145.000 X		=		
78001150	PAINT PVT MK LINE 12	FOOT	104.000 X		=		
78001180	PAINT PVT MK LINE 24	FOOT	40.000 X		=		
				TOTAL		\$	

NOTE:

1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

Revised 7/27/07