

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2770	D6-00100-00-RS	COOK	26	3
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 83953				

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY 1000-2A
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	70
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5200
40600300	AGGREGATE (PRIME COAT)	TON	50
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	420
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2250
42001300	PROTECTIVE COAT	SQ YD	950
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	280
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	70
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	800
42400800	DETECTABLE WARNINGS	SQ FT	110
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	26000
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	350
44000600	SIDEWALK REMOVAL	SQ FT	1000
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2260
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1000
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	240
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	500
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	4
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	1
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1
60251500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	1
60255500	MANHOLES TO BE ADJUSTED	EACH	2
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	23
60500050	REMOVING CATCH BASINS	EACH	5
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3400
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	380
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	260
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12500
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1700
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	500
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	140
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	40
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	40
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	480

X4067107 Polymerized Leveling Binder (Machine Method), IL 4.75, N50 TON 1080

* SPECIALITY ITEM

REVISIONS	
NAME	DATE

GC Giorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60658
Tel. 773.775.4009 Fax 773.775.4014 Email: chicago@giorba.com

VILLAGE OF MORTON GROVE

SHERMER ROAD
SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: CLG
DATE: MAY, 2007 CHECKED BY: MRJ

DATE: 05/07/07 TIME: 11:11 AM FILE: P:\PROJECTS\2007\20070507\Shermer Road\Summary of Quantities.dwg