

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
591	06-00034-00-RP	KENDALL	37	4
STA.		TO STA.		
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY
△ 88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3
△ 88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4
△ 88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	4
△ 88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	13
△ ○ 88500100	INDUCTIVE LOOP DETECTOR	EACH	9
△ 88600100	DETECTOR LOOP, TYPE I	FOOT	942
△ 88700200	LIGHT DETECTOR	EACH	4
△ 88700300	LIGHT DETECTOR AMPLIFIER	EACH	4
△ ○ 88800100	PEDESTRIAN PUSH-BUTTON	EACH	4
△ ○ 89502200	MODIFY EXISTING CONTROLLER	EACH	3
△ X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1538
△ X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	1538
△ X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	599
△ X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1008
△ XX002852	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1
○ Z0013798	CONSTRUCTION LAYOUT	L SUM	1

△ SPECIALTY ITEMS
○ SEE SPECIAL PROVISIONS

PLOT DATE = #DATE#
FILE NAME = #FILE#
PLOT SCALE = #SCALE#
USER NAME = #USER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 591 (US 34)
AND WAUBONSEE DRIVE
SECTION 06-00034-00-RP
KENDALL COUNTY

SCALE: VERT. DRAWN BY: NOE/NV
 HORIZ. CHECKED BY: DJD
DATE: 02/07