

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8146	06-00029-00-TL	SANGAMON	67	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT *		
* HS-8146(003)				

**PAVEMENT REMOVAL AND PATCHING SCHEDULE**

LOCATION	SAW CUTS	CURB REMOVAL	GUTTER REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	DRIVEWAY PAVEMENT REMOVAL	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL - VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	MEDIAN SURFACE REMOVAL AND REPLACEMENT	CLASS D PATCHING, TYPE II 9 INCH SQ YD	CLASS B PATCHING, TYPE II 13 INCH SQ YD
	FOOT	FOOT	FOOT	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	SQ FT	SQ YD	SQ YD
<b>WALNUT STREET (FAU 8146)</b>											
STA. 31+00 TO STA. 31+41								110			
STA. 31+41 TO STA. 32+09							70				
STA. 31+72, RT.					22			108			
STA. 31+76, LT. (FRONTAGE ROAD)											
STA. 32+20, 26' LT. TO STA. 32+25, 28' RT.	414									12.8	
STA. 32+32, LT. TO STA. 36+42, LT.						38					
STA. 32+95, RT.						105					
STA. 34+00 TO STA. 37+09							200				
STA. 34+05, 16' LT. TO STA. 34+05, 6' RT.										11.9	
STA. 35+25, 19' LT. TO STA. 35+25, 19' RT.										12.4	
STA. 36+00, LT.						52					
STA. 36+12, RT.						63					
STA. 36+43, LT. TO STA. 36+61, LT.	20										
STA. 37+92.7, LT. TO STA. 37+99.7, LT.		7									
STA. 37+99, LT. TO STA. 38+70, LT.	71										
STA. 38+75 TO STA. 40+75							250				
STA. 39+95, 19' LT TO STA. 39+95, 19' RT.										12.6	
STA. 40+71.5, 23' LT.				55	184				44		
STA. 42+15, 19' LT. TO STA. 42+15, 19' RT.										13.1	
STA. 43+40 TO STA. 44+35							140				
STA. 43+80, 19' LT. TO STA. 43+80, 19' RT.										13.1	
STA. 44+07, LT.						48					
STA. 44+69 TO STA. 45+00								83			
STA. 47+71, 23' LT.										18.6	
<b>PARK AVENUE (FAU 8153)</b>											
STA. 196+50, LT. TO STA. 199+96, LT.				362							
STA. 196+52, LT. TO STA. 196+82, LT.	32							83			
STA. 196+52 TO STA. 196+83											
STA. 196+83, RT. TO STA. 199+50, RT.							230				
STA. 197+00, 13.61' LT. TO STA. 197+00, 13.22' RT.										13.1	
STA. 197+28.5, LT.						69					
STA. 198+87, LT. TO STA. 199+85, LT.								39			
STA. 199+50, 27.40' LT. TO STA. 199+50, 23.10' RT.										16.7	
STA. 199+48, RT. TO STA. 199+59, RT.	13										
STA. 199+48, RT. TO STA. 199+94, RT.				101							
STA. 200+30.5	149										30.5
STA. 200+41, LT. TO STA. 201+66, LT.				125							
STA. 200+43, RT. TO STA. 201+66, RT.				123							
STA. 200+55, LT. TO STA. 200+63, LT.	10										
STA. 200+70, 21.10' LT. TO STA. 200+75, 24.30' RT.	158										32.4
STA. 200+72, RT. TO STA. 200+88, RT.	18										
STA. 201+19.50, RT.				36	79						
STA. 201+35 TO STA. 201+66								138			
STA. 201+36, LT.						14					
<b>TOTALS</b>	<b>885</b>	<b>7</b>	<b>248</b>	<b>554</b>	<b>531</b>	<b>182</b>	<b>890</b>	<b>522</b>	<b>44</b>	<b>124.3</b>	<b>62.9</b>

**STRUCTURE ADJUSTMENT SCHEDULE**

LOCATION	VALVE VAULTS TO BE ADJUSTED EACH	MANHOLES TO BE ADJUSTED EACH	MANHOLES TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE EACH
<b>WALNUT STREET (FAU 8146)</b>			
STA. 36+72.8, 13.8' RT. (GAS)	1		
STA. 36+81.4, 13.4' RT. (GAS)	1		
STA. 37+04.5, 33.6' LT. (GAS)	1		
STA. 37+14.2, 4.6' RT. (WATER)	1		
STA. 37+70.2, 15.4' RT. (GAS)	1		
STA. 37+87.5, 17.0' RT. (GAS)	1		
STA. 37+94.9, 11.7' RT. (GAS)	1		
STA. 38+08.2, 24.5' LT. (WATER)	1		
STA. 40+59.8, 20.7' LT. (WATER)	1		
<b>PARK AVENUE (FAU 8153)</b>			
STA. 197+74.83, 16' LT.			1
STA. 197+78.3, 1.4' RT.		1	
STA. 199+68.4, 5.3' LT.		1	
<b>TOTALS</b>	<b>9</b>	<b>2</b>	<b>1</b>

**TEMPORARY ACCESS SCHEDULE**

LOCATION	TEMPORARY ACCESS (PRIVATE ENTRANCE) EACH	TEMPORARY ACCESS (COMMERCIAL ENTRANCE) EACH	TEMPORARY ACCESS (ROAD) EACH
STA. 31+72.5, RT.	1		
STA. 32+95, RT.			1
STA. 36+00, LT.	1		
STA. 36+12, RT.	1		
STA. 40+72, LT.		1	
STA. 44+07, LT.		1	
STA. 197+28.7, LT.	1		
STA. 198+16.5, LT.	1		
STA. 201+20, RT.		1	
STA. 201+36, LT.	1		
<b>TOTALS</b>	<b>6</b>	<b>3</b>	<b>1</b>

PLOT DATE = 4/27/2007  
 FILE NAME = J:\06152\Drawings\06152SCH.dgn  
 PLOT SCALE = 262000 / 1 IN.  
 PLOTTER = HP DesignJet 5000  
 OPERATOR = Frank

REVISIONS	
NAME	DATE
IDOT REVIEW	4/11/07

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**

VILLAGE OF CHATHAM  
 SECTION 06-00029-00-TL  
 SANGAMON COUNTY  
 WALNUT ST. / PARK AVE. IMPROVEMENTS

VERT. SCALE: 1" = 20'  
 HORIZ. SCALE: 1" = 40'  
 DATE: 2/14/07

DRAWN BY: SUTHEARD  
 CHECKED BY: BOTT

GREENE & BRADFORD, INC.  
 OF SPRINGFIELD

COMPUTER FILE NO.  
 06152SCH

PROJECT 06152  
 4/11/07 - MML