

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8883	05-00090-01-TL	MADISON	39	2
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 87313				

GENERAL NOTES:

WHERE SECTION OR SUB-SECTION MARKERS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED OR COVERED UP. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATIONS.

ILLINOIS STATE LAW REQUIRES A 48-HR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.L.I.E. OR FOR NON-J.U.L.L.I.E. MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS

- CITY OF EDWARDSVILLE WATER & SEWER
118 HILSBORO AVENUE
P.O. BOX 407
EDWARDSVILLE, IL 62025
- AMEREN IP GAS & ELECTRIC
2600 NORTH CENTER STREET
P.O. BOX 378, MC-010
MARYVILLE, IL 62062-0378
ATTENTION: MARK HOLDENER
- AT&T TELEPHONE
203 GOETHE STREET
FLOOR 7 1/2
COLLINSVILLE, IL 62234
ATTENTION: TIM DREGENZIER
- CHARTER COMMUNICATIONS, INC. CABLE
941 CHARTER COMMONS
ST. LOUIS, MO 63107
ATTENTION: STEVE GERREIN

(MEMBERS OF J.U.L.L.I.E. (800) 892-0123 ARE INDICATED BY * NON-J.U.L.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY)

FOR UTILITY LOCATION PURPOSES, THIS PROJECT IS LOCATED IN SECTIONS 23 & 24 OF TOWNSHIP 4 NORTH, RANGE 8 WEST OF THE THIRD PRINCIPAL MERIDIAN.

TREES SHALL BE PRESERVED THROUGH OUT THIS SECTION AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER.

REMOVAL OF AGGREGATE MATERIAL AND OIL AND CHIP BITUMINOUS MATERIAL SHALL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE COST OF EARTH EXCAVATION.

THE CONTRACTOR SHALL CONSTRUCT PAVEMENT SO THAT FLOW ALONG CURBS AND/OR GUTTERS IS MAINTAINED, INCLUDING FLOW THROUGH INTERSECTIONS, AROUND CURB RETURNS AND TO EXISTING INLETS.

THE TOP OF PROPOSED P.C.C. CURB/CURB AND GUTTER SHALL BE CONSTRUCTED AT THE SAME ELEVATION AS THE TOP OF THE EXISTING CURB/CURB AND GUTTER. THIS SHALL BE DONE IN ORDER TO MAINTAIN THE EXISTING DRAINAGE PATTERN TO THE EXISTING INLETS AND TO MAINTAIN THE EXISTING PROFILE.

THE CONTRACTOR SHALL ADJUST WATER VALVES AND OTHER ITEMS LOCATED WITHIN THE EXISTING ROADWAY TO MATCH THE PROPOSED ROADWAY SURFACE. THIS WORK SHALL BE CONSIDERED INCLUDED IN THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ALL AREAS DISTURBED FOR ANY REASON SHALL BE SEEDED WITH CLASS 1 SEEDING AND MULCH, AS DIRECTED BY THE ENGINEER. NUTRIENTS SHALL CONFORM TO ARTICLE 250.04 AND WILL BE PAID FOR SEPARATELY.

A CURB RAMP SHALL BE CONSTRUCTED AT ALL INTERSECTIONS WHERE SIDEWALK IS PRESENT. RAMP SHALL BE CONSTRUCTED ACCORDING TO HIGHWAY STANDARD 424001.

THE CONTRACTOR SHALL REMOVE AND RELOCATE EXISTING MAILBOXES PER ARTICLE 107.20 OF THE STANDARD SPECIFICATIONS.

THE CONTRACTOR SHALL BE REQUIRED TO PERFORM SAWCUTTING AT THE EXISTING PAVEMENT, EXISTING WIDENING, OR EXISTING SHOULDER EDGE THROUGHOUT THE PROJECT LIMITS IN ORDER TO PERFORM REMOVAL OPERATIONS. THIS SAWING WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE COST FOR THE REMOVAL ITEM INVOLVED.

CHANGES IN THE VERTICAL OR HORIZONTAL DIMENSIONS OF GUTTERS, CURBS, OR CURB AND GUTTERS, WHEN TRANSITIONS FROM ONE TYPE TO ANOTHER AS SHOWN IN THE PLANS, WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR THE TYPE DESIGNATED IN THE PLAN SCHEDULE.

THE THICKNESS OF BITUMINOUS MIXTURES SHOWN ON THE PLANS IS THE AVERAGE THICKNESS. DEVIATIONS FROM THE AVERAGE THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

WHERE PROPOSED CONCRETE PAVEMENT OR PCC CURB AND GUTTER IS TO BE CONSTRUCTED ADJACENT TO EXISTING CONCRETE PAVEMENT OR PCC CURB AND GUTTER, THE CONTRACTOR SHALL DRILL AND GROUT NO. 6 X 30 EPOXY COATED TIE BARS AT 30" CENTERS. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF PCC PAVEMENT 8" (JOINTED) OR COMBINATION CONCRETE CURB AND GUTTER AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

THE REMOVAL OF ANY CURB/CURB AND GUTTER SHALL ALSO INCLUDE THE DISCONNECTION OF THE EXISTING CURB/CURB AND GUTTER FROM ANY REINFORCEMENT OR COLLATERAL MATERIAL THAT MAY BE PRESENTLY ATTACHED. THERE SHALL NOT BE ANY ADDITIONAL REMUNERATION BUT THIS WORK SHALL BE CONSIDERED AS INCLUDED IN THE REMOVAL ITEM.

THE FOLLOWING CONSTANTS WERE USED IN THE CALCULATION OF QUANTITIES FOR THIS PROJECT:

- MULCH 2 TONS/ACRE
- GRANULAR MATERIALS 2.05 TONS/C.Y.

ALL MANHOLE AND INLET LOCATIONS NOTED IN THE PLANS REFER TO THE BARREL SECTION OF THE STRUCTURES.

THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.

"ROAD CONSTRUCTION AHEAD" SIGNS (48"X48") SHALL BE PLACED AT THE BEGINNING AND END OF THE PROJECT PLUS THE INTERSECTING SIDE ROADS, AND WILL BE CONSIDERED INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR AN ON-SITE INSPECTION PRIOR TO SUBMITTING A BID ON THIS PROJECT. UPON RECEIPT OF A BID, IT SHALL BE ASSUMED THAT THE CONTRACTOR IS FULLY FAMILIAR WITH THE CONSTRUCTION SITE.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING THE FIRE DEPARTMENT AND POLICE DEPARTMENT OF THE RESPECTIVE MUNICIPALITY ANY TIME NORMAL TRAFFIC FLOW ON ANY STREET OR ROAD IS TO BE INTERRUPTED, HOWEVER BRIEFLY.


- CITY OF EDWARDSVILLE POLICE DEPARTMENT 618-656-2131 (NON-EMERGENCY)
- CITY OF EDWARDSVILLE FIRE DEPARTMENT 618-692-7541 (NON-EMERGENCY)
- MADISON COUNTY SHERIFF DEPARTMENT 618-692-4433 (NON-EMERGENCY)

LEGEND

- 5" EVERGREEN (5" DIA)
- 8" DECIDUOUS (8" DIA)
- EVERGREEN SHRUB
- SHRUB
- FIRE HYDRANT
- SIGN
- BOLLARD
- POWER POLE
- POWER POLE WITH DOWN GUY
- X-X- FENCE
- BENCH MARK
- - - DITCH/SWALE
- EXISTING MAILBOX
- FOUND CONCRETE MONUMENT
- WM WATER METER
- GM GAS METER
- WV WATER VALVE
- GV GAS VALVE
- (TBA) TO BE ADJUSTED
- (TBR) TO BE REMOVED
- (TBR&R) TO BE REMOVED & RELOCATED
- (TBR&R&O) TO BE REMOVED & RELOCATED BY OTHERS
- DND DO NOT DISTURB
- P — PROPERTY LINE
- — — EXIST R.O.W. LINE
- ⊗ WOOD POST
- W — WATER LINE
- G — GAS LINE
- OHE — OVERHEAD ELECTRIC LINE
- T — TELEPHONE LINE
- CTV — CABLE TV LINE
- S — STORM SEWER
- SS — SANITARY SEWER
- LIGHT POLE
- STORM SEWER MANHOLE
- SANITARY SEWER MANHOLE
- CATCH BASIN
- INLET

DATE	BY	SURVEYED	REVISIONS
		PLANNED	
		FIELD	
		NOTE BOOK	
		AREAS CHECKED	
		NO.	

DATE	BY	ORIGINAL	REVISIONS
		SURVEY	
		FIELD	
		NOTE BOOK	
		AREAS CHECKED	
		NO.	

 Juneau Associates, Inc. P.C. CONSULTING ENGINEERS AND LAND SURVEYORS 2700 Stone Street, P.O. Box 5320 Granite City, Illinois 62040 Phone: (618) 877-4400 / (618) 452-5371 Fax: (618) 452-5341		GENERAL NOTES F.A.U. ROUTE 8883 & 8873 GOSHEN AND OLD TROY ROADS EDWARDSVILLE, ILLINOIS SECTION No. 05-00090-01-TL									
REVISIONS <table border="1"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>BY</th> <th>REMARKS</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		NO.	DATE	BY	REMARKS					SCALE: N.T.S.	
NO.	DATE	BY	REMARKS								
DSN. BY: BFK DWN. BY: DAN CHK'D: BFK		DATE: 03/08/07 DATE: 03/08/07 DATE: 03/08/07									
DWG. NO.		JOB NO. E063800 DGN. NAME: GENNOTES OF 39 SHEETS									