

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	898
20800150	TRENCH BACKFILL	CU YD	12
25000100	SEEDING, CLASS 1	ACRE	0.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23
25100120	MULCH, METHOD 2	TON	0.5
28000500	INLET AND PIPE PROTECTION	EACH	12
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1508
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	1095
42001200	PAVEMENT FABRIC	SQ YD	1095
42001300	PROTECTIVE COAT	SQ YD	2261
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	274
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	5835
42400800	DETECTABLE WARNINGS	SQ FT	37
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	342
44000300	CURB REMOVAL	FOOT	54
44000400	GUTTER REMOVAL	FOOT	58
44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	1093
44000600	SIDEWALK REMOVAL	SQ FT	3355
54200637	PIPE CULVERTS, TYPE I, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE, 12"	FOOT	71
54213447	END SECTIONS, 12"	EACH	1
55019600	STORM SEWERS, TYPE I, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	21
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	4
60242900	INLETS, SPECIAL, TYPE I	EACH	1
60260200	INLETS TO BE ADJUSTED (SPECIAL)	EACH	3
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE I, FRAME, CLOSED LID	EACH	1
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3, FRAME AND GRATE	EACH	1


SUMMARY OF QUANTITIES			
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
60261530	INLETS TO BE ADJUSTED WITH NEW TYPE 23, FRAME AND GRATE	EACH	1
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1206
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4600
70300210	TEMPORARY PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	125
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	3546
70300240	TEMPORARY PAVEMENT MARKING-LINE 6"	FOOT	266
70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	369
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1521
72000100	SIGN PANEL-TYPE 1	SQ FT	8
72000200	SIGN PANEL-TYPE 2	SQ FT	21
* 78008200	POLYUREA PAVEMENT MARKING TYPE I-LETTERS & SYMBOLS	SQ FT	125
* 78008210	POLYUREA PAVEMENT MARKING TYPE I-LINE 4"	FOOT	3546
* 78008230	POLYUREA PAVEMENT MARKING TYPE I-LINE 6"	FOOT	266
* 78008250	POLYUREA PAVEMENT MARKING TYPE I-LINE 12"	FOOT	369
* 80500105	SERVICE INSTALLATION, TYPE A (MODIFIED)	EACH	1
* 81012100	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	47
* 81012500	CONDUIT IN TRENCH, 1-1/2" DIA., PVC	FOOT	30
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	30
* 81012700	CONDUIT IN TRENCH, 2-1/2" DIA., PVC	FOOT	15
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	100
* 81012900	CONDUIT IN TRENCH, 3-1/2" DIA., PVC	FOOT	7
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	3
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	49
* 81018600	CONDUIT PUSHED, 2-1/2" DIA., GALVANIZED STEEL	FOOT	58
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	4
* 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	232

SUMMARY OF QUANTITIES			
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	752
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	780
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1337
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	464
* 87301405	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 16 1 PAIR	FOOT	875
* 87301815	ELECTRIC CABLE IN CONDUIT, SERVICE NO. 6 3C	FOOT	30
* 87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	1
* 87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1
* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1
* 87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3
* 87800210	CONCRETE FOUNDATION, TYPE D (SPECIAL)	FOOT	3
* 87800415	CONCRETE FOUNDATION, TYPE E 36" DIAMETER	FOOT	37
* 88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3
* 88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4
* 88040110	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	1
* 88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	1
* 88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1
* 88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1
* 88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	4
* 88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	6
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	5
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	909
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	4
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	572

BY: _____ DATE: _____
 ORIGINAL SURVEY PLOTTED _____
 NOTE BOOK TEMPLATE AREAS CHECKED _____
 NO. _____

BY: _____ DATE: _____
 ORIGINAL SURVEY PLOTTED _____
 NOTE BOOK TEMPLATE AREAS CHECKED _____
 NO. _____

* SPECIALTY ITEMS

 Juneau Associates, Inc. P.C. CONSULTING ENGINEERS AND LAND SURVEYORS <small>200 State Street, P.O. Box 1205, Granite City, Illinois 62040 Phone: (618) 883-8800 Fax: (618) 883-8801 100 North Main Street, Edwardsville, Illinois 62025 Phone: (618) 883-0800 Fax: (618) 883-0801</small>		SUMMARY OF QUANTITIES F.A.U. ROUTE 8883 & 8873 GOSHEN AND TROY ROADS EDWARDSVILLE, ILLINOIS SECTION No. 05-00090-01-TL																	
REVISIONS <table border="1"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>BY</th> <th>REMARKS</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>		NO.	DATE	BY	REMARKS													SCALE: NOT TO SCALE DSN. BY: BFK DATE: 12/15/05 DWN. BY: DAN DATE: 12/15/05 CHKD: BFK DATE: 12/15/05 DWG. NO.	
NO.	DATE	BY	REMARKS																
		SHEET <div style="border: 1px solid black; width: 20px; height: 20px; display: flex; align-items: center; justify-content: center; margin: 0 auto;">3</div> JOB NO. E063800 DGN. NAME: PCOMSCH OF 39 SHTS																	