

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8883	05-00090-01-TL	MADISON	39	10
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 97213				

PAVING SCHEDULE

LOCATION	PCC PVT 8 IN (JTD.) (SQ YD)	SUB BASE GRANULAR TY A 4 IN (SQ YD)	PAVEMENT FABRIC (SQ YD)	PROT COAT (SQ YD)
GOSHEN ROAD				
STA. 102+71.29 TO STA. 102+85.16 RT	1.1	4.6	1.1	1.1
STA. 102+85.16 TO STA. 106+30.89 RT	283.3	401.7	283.3	283.3
STA. 108+49.58 TO STA. 114+11.72 RT	501.7	694.5	501.7	501.7
OLD TROY ROAD				
STA. 250+11.13 TO STA. 251+36.41 RT	134.6	181.7	134.6	134.6
STA. 251+36.41 TO STA. 251+66.39 RT	1.7	1.7	1.7	1.7
STA. 250+88.61 TO STA. 250+15.07 LT	172.3	224.4	172.3	172.3
TOTAL	1095	1508	1095	1095

P.C.C. CURB AND GUTTER SCHEDULE

LOCATION	C & G TYPE B-6.18 (FOOT)
GOSHEN ROAD	
STA. 102+74.81-22.45' RT TO STA. 104+66.57-49.53' RT	217.9
STA. 105+01.59-49.53' RT TO STA. 106+30.87-25.50' RT	149.4
STA. 107+57.03-41.93' RT TO STA. 109+87.71-44.62' RT	244.7
STA. 110+23.56-44.64' RT TO STA. 114+11.72-14.41' RT	399.4
OLD TROY ROAD	
STA. 250+24.18-71.70' RT TO STA. 251+36.39-14.50' RT	137.9
STA. 250+88.61-27.35' LT TO STA. 250+43.35-53.93' LT	56.4
TOTAL	1206

ENTRANCE SCHEDULE

LOCATION	WIDTH (FOOT)	PCC DRIVEWAY PAVEMENT 8 IN (SQ YD)	DISTANCE (FOOT)
GOSHEN ROAD			
CE @ 103+04.82 RT	26.3	31.2	3.1
CE @ 103+70.15 RT	24.0	32.3	3.1
CE @ 104+83.18 RT	32.0	116.9	
CE @ 110+05.32 RT	32.9	93.1	
TOTAL		274	

P.C.C. SIDEWALK SCHEDULE

LOCATION	PCC SIDEWALK (SQ FT)
GOSHEN ROAD	
STA. 105+04.15 - 29.64' RT TO STA. 106+30.89 - 32.08' RT	745.7
STA. 106+49.68 - 17.80' LT TO STA. 107+70.45 - 17.42' LT	465.7
STA. 108+37.38 - 32.08' RT TO STA. 109+83.77 - 32.58' RT	861.4
STA. 110+27.50 - 32.58' RT TO STA. 114+11.72 - 20.90' RT	2206.6
OLD TROY ROAD	
STA. 250+30.75 - 71.85' RT TO STA. 251+36.39 - 21.08' RT	794.4
STA. 250+83.61 - 34.85' LT TO STA. 250+34.43 - 135.16' LT	761.5
TOTAL	5835

PROTECTIVE COAT SCHEDULE

LOCATION	PROT. COAT (SQ YD)
PORTLAND CEMENT CONCRETE PAVEMENT	1094.5
COMBINATION CURB AND GUTTER, B-6.18	268.0
DRIVEWAY PAVEMENT	273.5
6' PCC SIDEWALK	624.5
TOTAL	2261

DETECTABLE WARNINGS SCHEDULE

LOCATION	AREA (SQ FT)
GOSHEN ROAD	
STA. 107+50.27-17.41' LT TO STA. 107+54.27-17.41' LT	7.82
OLD TROY ROAD	
STA. 250+44.50-39.26' RT TO STA. 250+49.43-36.36' RT	11.73
STA. 250+45.63-54.78' LT TO STA. 250+50.19-46.39' LT	17.63
TOTAL	37

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-) (CU YD)
ROADS	898	674	20	654
TOTAL	898	674	20	654

NOTE: BASED ON 25% SHRINKAGE

SEEDING SCHEDULE

LOCATION	SEEDING CLASS 1 (AC)	NITROGEN FERT NUTR (LB)	PHOSPHORUS FERT NUTR (LB)	POTASSIUM FERT NUTR (LB)	MULCH METHOD 2 (TON)
GOSHEN ROAD					
STA. 102+75.39 TO STA. 114+11.72	0.25	22.5	22.5	22.5	0.5
TOTAL	0.25	23	23	23	0.5

Juneau Associates, Inc. P.C.
 CONSULTING ENGINEERS AND LAND SURVEYORS
 2000 State Street, P.O. Box 1522 / Old North Hancock Drive
 Edwardsville, Illinois 62026 / Edwardsville, Illinois 62026
 Phone: (618) 695-1400 / (618) 695-1400 / Fax: (618) 695-0941

QUANTITY SCHEDULES
 F.A.U. ROUTE 8883 & 8873
 GOSHEN AND OLD TROY ROADS
 EDWARDSVILLE, ILLINOIS
 SECTION No. 05-00090-01-TL

REVISIONS				SCALE:
NO.	DATE	BY	REMARKS	NOT TO SCALE

DSN. BY: BFK	DATE: 3/08/07	SHEET 10	
DWN. BY: DAN	DATE: 3/08/07		
CHK'D: BFK	DATE: 3/08/07		
DWG. NO.	JOB NO. E063800	DGN. NAME: PCOMSCH	OF 39 SHTS

DATE _____
 BY _____
 ORIGINAL SURVEY PLOTTED _____
 SURVEY PLOTTED _____
 NOTE BOOK TEMPLATE _____
 AREAS CHECKED _____
 NO. _____

DATE _____
 BY _____
 ORIGINAL SURVEY PLOTTED _____
 SURVEY PLOTTED _____
 NOTE BOOK TEMPLATE _____
 AREAS CHECKED _____
 NO. _____