

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-) (CU YD)
BISSELL ST	6541	4906	327	(+) 4579
IL RTE 3	444	333	1632	(-) 1299
TOTAL	6985	5239	1959	3280

NOTE: BASED ON 25% SHRINKAGE

PIPE CULVERT SCHEDULE

STRUCTURE ID	LOCATION	PRECAST RCCP ELLIPTICAL, EQUIV. ROUND SIZE 18" (FOOT)	TRENCH BACKFILL (CU YD)
	BISSELL STREET		
FES-1 TO FES-2	STA. 127+16.84 - 26.44' LT TO STA. 127+16.84 - 27.94' RT	43	4
FES-3 TO FES-4	STA. 133+70.00 - 27.50' LT TO STA. 133+70.00 - 27.80' RT	43	3
FES-5 TO S-1	STA. 136+71.90 - 67.62' LT TO STA. 136+71.90 - 25.50' RT	34	1
S-1 TO FES-6	STA. 136+71.90 - 67.62' LT TO STA. 136+71.84 - 39.00' RT	57	6
FES-10 TO FES-11	STA. 140+53.89 - 53.03' LT TO STA. 141+00.00 - 35.11' LT	37	
TOTAL		214	14

PAVEMENT MARKING SCHEDULE

LOCATION	TYPE	POLYUREA PAVEMENT MARKINGS					THERMOPLASTIC PAVEMENT MARKINGS					PREFORMED PLASTIC PAVEMENT MARKINGS TYPE B			RAISED REFLECTIVE PAVEMENT MARKINGS			PRISMATIC CURB REFLECTOR (EACH)	PAINT PAVEMENT MARKING RAISED MEDIAN (SQ FT)	PAINT PAVEMENT MARKING CURB (FOOT)			
		4" YELLOW (FOOT)	4" WHITE (FOOT)	8" WHITE (FOOT)	12" YELLOW (FOOT)	12" WHITE (FOOT)	4" YELLOW (FOOT)	4" WHITE (FOOT)	8" WHITE (FOOT)	12" WHITE (FOOT)	12" WHITE (FOOT)	24" WHITE (FOOT)	LETTERS AND SYMBOLS (SQ FT)	ONE-WAY		TWO-WAY							
														AMBER (EACH)	CRYSTAL (EACH)	AMBER (EACH)							
BISSELL STREET																							
STA. 116+00.00 TO STA. 147+30.89																							
	SKIP-DASH 10'-30'	475																					
	DOUBLE CENTER LINE	2872																					
	LANE LINE		675	281																			
	EDGE LINE	658	6402																				
	SKIP-DASH 2'-6'		29																				
	STOP BARS										102	60											
	DIAGONALS				315	311																	
	ARROWS												202										
	RAILROAD CROSSINGS												122										
ILLINOIS ROUTE 3																							
STA. 109+00.00 TO STA. 111+00.00																							
	LANE LINE																						
	EDGE LINE										347	574							19		3		
	STOP BARS											532	183										
	SKIP-DASH 2'-6'											133											
	DIAGONALS																						
	ARROWS																						
TOTAL		4005	7106	281	315	311	347	1239	183	33	102	159	371	39	55	24	26	69	749				

STORM SEWER SCHEDULE

STRUCTURE ID	LOCATION	STORM SEWERS, RCCP, STORM DRAIN, AND SEWER PIPE				TRENCH BACKFILL (CU YD)
		TYPE I CLASS IV 15" (FOOT)	TYPE I CLASS IV 24" (FOOT)	TYPE I CLASS II 48" (FOOT)	TYPE I CLASS I 60" (FOOT)	
	BISSELL STREET					
S-2 TO S-3	STA. 139+00.00 - 25.91' LT TO STA. 139+69.30 - 36.75' LT		63			0.0
S-3 TO S-4	STA. 139+69.30 - 36.75' LT TO STA. 139+69.30 - 38.75' RT				66	44.0
S-4 TO FES-7	STA. 139+69.30 - 38.75' RT TO STA. 139+69.30 - 58.00' RT				6	0.0
S-3 TO FES-8	STA. 139+69.30 - 36.75' LT TO STA. 140+43.81 - 55.39' LT			64		36.0
FES-9 TO S-5	STA. 146+13.47 - 85.18' LT TO STA. 146+16.25 - 34.16' LT	44				0.0
S-5 TO S-6	STA. 146+16.32 - 34.16' LT TO STA. 146+16.25 - 42.40' RT	74				14.0
TOTAL		118	63	64	72	94

SEEDING SCHEDULE

LOCATION	SEEDING CLASS 1 (AC)	NITROGEN FERT NUTR (LB)	PHOSPHORUS FERT NUTR (LB)	POTASSIUM FERT NUTR (LB)	MULCH METHOD 2 (AC)
BISSELL STREET					
STA. 116+00.00 - STA. 147+30.89	3.2	289.8	289.8	289.8	3.2
TOTAL	3	290	290	290	3

Juneau Associates, Inc. P.C.
CONSULTING ENGINEERS AND LAND SURVEYORS
2100 North Street, P.O. Box 1325
Channahon, IL 61018-1325
Phone: (815) 421-1111 Fax: (815) 421-1111
FAX: (815) 421-1111

QUANTITY SCHEDULES
BISSELL STREET
MADISON, ILLINOIS
SECTION No. 05-00001-00-WR

REVISIONS			
NO.	DATE	BY	REMARKS

SCALE: NOT TO SCALE			
DSN. BY: BFK	DATE: 1/19/07	SHEET	
DWN. BY: RKR	DATE: 1/19/07	21	
CHK'D: BFK	DATE: 1/19/07		
JOB NO. E061300 DGN. NAME: COMBSCH OF 102 SHTS			

BY: _____ DATE: _____
ORIGINAL SURVEYED SURVEY PLOTTED NOTE BOOK TEMPLATE AREAS CHECKED NO. _____

BY: _____ DATE: _____
ORIGINAL SURVEYED SURVEY PLOTTED NOTE BOOK TEMPLATE AREAS CHECKED NO. _____