

### CONCRETE MEDIAN SURFACE SCHEDULE

LOCATION	CONCRETE MEDIAN SURFACE, 4 INCH (SQ FT)
BISSELL STREET	
STA. 144+02.66 - 03.82' LT TO STA. 147+20.86 - 01.60' LT	2854.5
STA. 146+95.80 LT TO STA. 147+11.60 LT	106.9
STA. 147+11.24 RT TO STA. 147+28.09 RT	105.8
<b>TOTAL</b>	<b>3067</b>

### GUARDRAIL REMOVAL SCHEDULE

LOCATION	GUARDRAIL REMOVAL (FOOT)
BISSELL STREET	
STA. 144+23.62 - 52.80' LT TO STA. 145+27.18 - 50.06' LT	103.6
STA. 144+29.08 - 54.36' RT TO STA. 144+58.38 - 30.64' RT	37.7
<b>TOTAL</b>	<b>141</b>

### ISLAND REMOVAL SCHEDULE

LOCATION	ISLAND REMOVAL (SQ FT)
BISSELL STREET	
STA. 146+95.26 LT TO STA. 147+12.46 LT	180.1
STA. 147+09.20 RT TO STA. 147+28.00 RT	205.1
<b>TOTAL</b>	<b>385</b>

### CHAIN LINK FENCE REMOVAL SCHEDULE

LOCATION	CHAIN LINK FENCE REMOVAL (FOOT)
BISSELL STREET	
STA. 140+25.05 - 72.69' LT TO STA. 140+24.97 - 43.38' LT	29.3
STA. 140+24.97 - 43.38' LT TO STA. 142+83.23 - 43.73' LT	258.3
STA. 142+83.23 - 43.73' LT TO STA. 142+81.69 - 51.95' RT	95.7
STA. 142+81.69 - 51.95' RT TO STA. 143+07.95 - 52.81' RT	26.3
STA. 145+27.65 - 60.32' RT TO STA. 145+28.26 - 75.28' LT	135.6
<b>TOTAL</b>	<b>545</b>

### PAVEMENT REMOVAL SCHEDULE

LOCATION	REMOVAL AREA (SQ YD)
BISSELL STREET	
STA. 120+19.48 TO STA. 127+78.01	3107.0
STA. 133+78.03 TO STA. 139+96.53	1658.5
STA. 144+22.28 TO STA. 147+20.67	2060.3
ILLINOIS ROUTE 3	
STA. 102+92.44 TO STA. 110+63.50	941.8
STA. 111+87.85 TO STA. 115+34.30	81.7
<b>TOTAL</b>	<b>7849</b>

### MEDIAN REMOVAL SCHEDULE

LOCATION	MEDIAN REMOVAL (SQ FT)
ILLINOIS ROUTE 3	
STA. 111+87.85 RT TO STA. 114+52.43 RT	940.1
<b>TOTAL</b>	<b>940</b>

### STRUCTURE REMOVAL SCHEDULE

LOCATION	INLET REMOVAL (EACH)
BISSELL STREET	
STA. 127+21.18 - 26.45' LT	1
STA. 139+29.31 - 17.97' LT	1
STA. 146+12.90 - 27.36' RT	1
STA. 146+12.90 - 34.93' LT	1
<b>TOTAL</b>	<b>4</b>

### CURB AND GUTTER REMOVAL SCHEDULE

LOCATION	CURB TYPE B (FOOT)	CURB & GUTTER	
		TYPE B-6.24 (FOOT)	TYPE B-6.12 (FOOT)
BISSELL STREET			
STA. 140+16.06 - 43.71' LT TO STA. 140+15.27 - 71.49' LT	27.8		
STA. 144+05.04 - 34.03' RT TO STA. 147+43.57 - 118.21' RT		380.3	
STA. 144+06.82 - 52.99' LT TO STA. 146+79.52 - 152.47' LT		382.2	
STA. 144+93.54 - 20.51' LT TO STA. 144+93.34 - 01.54' RT			22.1
STA. 144+93.34 - 01.54' RT TO STA. 147+20.78 - 01.20' RT			227.4
STA. 144+93.54 - 20.51' LT TO STA. 147+19.61 - 02.41' LT			228.3
ILLINOIS ROUTE 3			
STA. 111+87.85 - 07.80' RT TO STA. 114+52.43 - 00.83' LT	264.8		
<b>TOTAL</b>	<b>293</b>	<b>763</b>	<b>478</b>

### PIPE CULVERT REMOVAL SCHEDULE


LOCATION	PIPE CULVERT REMOVAL			TRENCH BACKFILL (CU YD)
	12" (FOOT)	15" (FOOT)	36" (FOOT)	
BISSELL STREET				
STA. 127+21.15 - 27.76' LT TO STA. 127+20.32 - 26.03' RT	54.0			10
STA. 129+13.00 - 20.66' LT TO STA. 129+73.94 - 19.66' LT		61.0		10
STA. 139+29.36 - 12.17' LT TO STA. 139+32.09 - 35.42' RT		48.0		16
STA. 139+70.52 - 38.17' RT TO STA. 140+47.70 - 54.97' LT			121.0	120
STA. 139+73.27 - 40.43' RT TO STA. 140+50.05 - 52.89' LT			121.0	119
STA. 146+12.90 - 27.36' RT TO STA. 146+12.90 - 34.93' LT		62.3		57
STA. 146+12.90 - 34.93' LT TO STA. 146+13.31 - 82.93' LT		48.0		0
<b>TOTAL</b>	<b>54</b>	<b>219</b>	<b>242</b>	<b>332</b>

### FENCE TO BE REMOVED AND RE-ERECTED

LOCATION	FENCE TO BE REMOVED AND RE-ERECTED (FOOT)
ILLINOIS ROUTE 3	
STA. 104+36.02 - 115.51' RT TO STA. 106+50.32 - 113.44' RT	215.0
<b>TOTAL</b>	<b>215</b>

### PAVEMENT MARKING REMOVAL SCHEDULE

LOCATION	24" STOP BAR REMOVAL (SQ FT)
ILLINOIS ROUTE 3	
STA. 110+17.57 RT TO STA. 110+18.27 LT	100.0
<b>TOTAL</b>	<b>100</b>

 <b>Juneco Associates, Inc. P.C.</b> CIVIL, TRAFFIC ENGINEERS AND LAND SURVEYORS 2100 State Street, P.O. Box 1325 Granite City, Illinois 62040 Phone: (618) 937-1400 / (618) 937-0200 Fax: (618) 937-0841		<b>QUANTITY SCHEDULES</b> <b>BISSELL STREET</b> <b>MADISON, ILLINOIS</b> <b>SECTION No. 05-00001-00-WR</b>									
<b>REVISIONS</b> <table border="1"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>BY</th> <th>REMARKS</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		NO.	DATE	BY	REMARKS					SCALE: NOT TO SCALE DSN. BY: BFK DATE: 1/19/07 DWN. BY: RKR DATE: 1/19/07 CHKD: BFK DATE: 1/19/07 JOB NO. E061300 DGN. NAME: COMBSCH OF 102 SHTS	
NO.	DATE	BY	REMARKS								
DWG. NO.		SHEET <b>22</b>									

DATE \_\_\_\_\_  
 BY \_\_\_\_\_  
 ORIGINAL SURVEY PLOTTED \_\_\_\_\_  
 NOTE BOOK TEMPLATE \_\_\_\_\_  
 AREAS CHECKED \_\_\_\_\_  
 NO. \_\_\_\_\_

DATE \_\_\_\_\_  
 BY \_\_\_\_\_  
 ORIGINAL SURVEY PLOTTED \_\_\_\_\_  
 NOTE BOOK TEMPLATE \_\_\_\_\_  
 AREAS CHECKED \_\_\_\_\_  
 NO. \_\_\_\_\_