

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
869	4B-1	FRANKLIN	56	7
STA.		TO STA.		
FED. ROAD DIST. NO. -	ILLINOIS	FED. AID PROJECT		

SEEDING AND FERTILIZING SCHEDULE

SN 028-2016 LOCATION STATION TO STATION	SEEDING CLASS 2	SEEDING CLASS 7	NITROGEN (N)	PHOSPHOROUS (P)	POTASSIUM (K)	MULCH METHOD 2	AGRICULTURAL GROUND LIMESTONE	TEMPORARY EROSION CONTROL SEEDING
	ACRES	ACRES	POUND	POUND	POUND	ACRES	TON	POUND
FAP 869 (IL 14)								
STA 577+09 LT TO STA 581+88 LT	0.1	0.1	16	12	12	0.2	0.2	10
STA 576+36 RT TO STA 581+12 RT	0.1	0.1	16	12	12	0.2	0.2	10
TOTALS	0.2	0.2	32	24	24	0.4	0.4	20

PAVING SCHEDULE

SN 028-2016 LOCATION STATION TO STATION	HOT-MIX ASPHALT SHOULDERS SUPERPAVE - 8''	PCC PAVEMENT 10'' (JOINTED)	HOT-MIX ASPHALT SHOULDERS SUPERPAVE - 10''	HOT-MIX ASPHALT BASE COURSE WIDENING - 10''
	SQ YD	SQ YD	SQ YD	SQ YD
FAP 869 (IL 14)				
STAGE I				
STA 576+36 RT TO STA 577+75 RT	158.3			
STA 577+75 RT TO STA 580+30 RT			298	
STA 580+30 RT TO STA 581+12 RT	82.7			
STA 578+72.50 RT TO STA 579+37 RT		86.8		
TOTAL ON RIGHT SIDE	241.0	86.8	298.0	0.0
PRE STAGE I				
STA 577+65 LT TO STA 578+94 LT				100
STA 579+16 LT TO STA 580+40 LT				97
STAGE II				
STA 577+09 LT TO STA 581+88 LT	595			
STA 578+72 LT TO STA 579+37 LT		72.2		
TOTAL ON LEFT SIDE	595	72.2	0.0	197
TOTALS	836	159	298	197

MARKING SCHEDULE

SN 028-2016 LOCATION STATION TO STATION	TEMP PVT MK LINE 4''		PAINT PVT MK LINE 4''		SHORT - TERM PAVEMENT MARKING
	WHITE	YELLOW	WHITE	YELLOW	
	FOOT	FOOT	FOOT	FOOT	
FAP 869 (IL 14)					
PRE STAGE I					
STA 577+42 LT TO STA 580+66 LT	324				
STA 577+42 CL TO STA 580+66 CL		324			
STAGE I					
STA 577+55 RT TO STA 580+54 RT	299				
STA 577+55 CL TO STA 580+54 CL		299			
POST STAGE II					
STA 577+42 LT TO STA 580+66 LT			324		
STA 577+55 RT TO STA 580+54 RT			299		
STA 575+50 CL TO STA 582+45 CL				174	72
TOTALS	623	623	623	174	72

5/4/2007
 c:\projects\900485\900485.dwg
 56,0000 / IN.
 PLOT