

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
869	104B-2	FRANKLIN	56	28
STA.		TO STA.		
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT	

MARKING SCHEDULE

SN 028-0076 LOCATION STATION TO STATION	TEMP PVT MK LINE 4''		PAINT PVT MK LINE 4''		SHORT -TERM PAVEMENT MARKING FOOT
	WHITE FOOT	YELLOW FOOT	WHITE FOOT	YELLOW FOOT	
FAP 869 (IL 14)					
PRE STAGE I					
STA 602+30 LT TO STA 605+30 LT	300				
STA 602+30 CL TO STA 605+30 CL		300			
STAGE I					
STA 601+62 RT TO STA 605+99 RT	437				
STA 601+62 CL TO STA 605+99 CL		437			
POST STAGE II					
STA 601+62 RT TO STA 605+99 RT			437		
STA 601+62 LT TO STA 605+99 LT			437		
STA 599+70 CL TO STA 607+90 CL				820	82
STA 599+70 CL TO STA 607+90 CL				205 (SKIPPED)	
TOTALS	737	737	874	1025	82

SEEDING AND FERTILIZING SCHEDULE

SN 028-0076 LOCATION STATION TO STATION	SEEDING CLASS 2	SEEDING CLASS 7	NITROGEN (N)	PHOSPHOROUS (P)	POTASSIUM (K)	MULCH METHOD 2	AGRICULTURAL GROUND LIMESTONE	TEMPORARY EROSION CONTROL SEEDING
	ACRES	ACRES	POUND	POUND	POUND	ACRES	TON	POUND
STA 601+41 LT TO STA 605+78 LT	0.2	0.2	32	24	24	0.40	0.4	20
STA 600+47 RT TO STA 606+36 RT	0.2	0.2	32	24	24	0.40	0.4	20
TOTALS	0.4	0.4	64	48	48	0.80	0.80	40

SHOULDER SCHEDULE

SN 028-0076 LOCATION STATION TO STATION	HOT-MIX ASPHALT SHOULDERS, 8''	HOT-MIX ASPHALT SHOULDERS, 10''	HOT-MIX ASPHALT BASE COURSE WIDENING - 10''
	SQ YD	SQ YD	SQ YD
FAP 869 (IL 14)			
STAGE I			
STA 600+47 RT TO STA 602+05 RT	219		
STA 602+05 RT TO STA 603+37 RT		143	
STA 604+24 RT TO STA 605+60 RT		145	
STA 605+60 RT TO STA 606+36 RT	89		
TOTAL ON RIGHT SIDE	308	288	0
PRE STAGE I			
STA 602+50 LT TO STA 603+58.5 LT			48
STA 604+01.5 LT TO STA 605+10 LT			49
STAGE II			
STA 601+41 LT TO STA 603+36 LT	174		
STA 604+23 LT TO STA 605+78 LT	156		
TOTAL ON LEFT SIDE	330	0	97
PROJECT TOTALS	638	288	97