

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	HBP FUNDING 80% FEDERAL 20% STATE
			CONSTRUCTION TYPE CODE X080-2A
25000210	SEEDING, CLASS 2A	ACRE	0.1
25000350	SEEDING, CLASS 7	ACRE	0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.2
25100115	MULCH, METHOD 2	ACRE	0.2
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20
28000400	PERIMETER EROSION BARRIER	FOOT	300
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	12
40600100	BITUMINOUS MATERIAL (PRIME COAT)	GALLON	50
40600300	AGGREGATE (PRIME COAT)	TON	0.8
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	290
40600990	TEMPORARY RAMP	SQ YD	88
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	39
44000100	PAVEMENT REMOVAL	SQ YD	12
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	115
48101200	AGGREGATE SHOULDERS, TYPE B	TON	8
48203100	HOT-MIX ASPHALT SHOULDERS	TON	12
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
50300260	BRIDGE DECK GROOVING	SQ YD	383
50300300	PROTECTIVE COAT	SQ YD	383
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	194
50400205	PRECAST PRESTRESSED CONCRETE DECK BEAMS (11" DEPTH)	SQ FT	3039
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4740
50800515	BAR SPLICERS	EACH	92
50901050	STEEL RAILING, TYPE SM	FOOT	228
50901125	STEEL RAILING (TEMPORARY)	FOOT	176
51500100	NAME PLATES	EACH	1
58700300	CONCRETE SEALER	SQ FT	80
59000200	EPOXY CRACK INJECTION	FOOT	114
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	176
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	124

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	HBP FUNDING 80% FEDERAL 20% STATE
			CONSTRUCTION TYPE CODE X080-2A
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	786
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	304
70400100	TEMPORARY CONCRETE BARRIER	FOOT	300
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	300
70500690	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE II	EACH	4
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	786
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	1
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	2
78300100	PAVEMENT MARKING REMOVAL	SQ FT	190
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	231
X0325326	TEMPORARY TRAFFIC CONTROL REMOVAL	L SUM	1
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	383
XX006681	UNINTERRUPTABLE POWER SUPPLY	EACH	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2

* SPECIALTY ITEM

FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	(105X)BR	WHITE	42	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ESCA
CONSULTANTS, INC.

DESIGNED BY:	MTD	02/07
DRAWN BY:	HAG	02/07
CHECKED BY:	MTD	02/07
APPROVED BY:	RDP	04/07

SUMMARY OF QUANTITIES
FAP RTE 328 (US 45)
SECTION (105X)BR
WHITE COUNTY