

LE038



HANSON PROFESSIONAL SERVICES INC.

815 Commerce Drive, Suite 200
Oak Brook, Illinois 60523
Telephone: 630.990.3800
Fax: 630.990.3801

Illinois Professional Design Firm
Registration No. 184-001084

© Copyright Hanson Professional Service Inc. 2007



JOLIET REGIONAL PORT DISTRICT

1 George Michas Drive
Romeoville, Illinois 60446
Telephone: 815.838.9497
Fax: 815.838.9524

REMOVE AND REPLACE PORTIONS
OF RUNWAY 9-27 AND TAXIWAY C

AIP PROJECT NO. 3-17-0140-B41
IDA PROJECT NO. LOT-3709

SUMMARY OF QUANTITIES - BASE BID

Item			Quantity	
Number	Description	Unit	Bid	Paid
AR125941	Adjust Stake Mounted Light	Each	7.00	
AR125942	Adjust Base Mounted Light	Each	3.00	
AR150510	Engineer's Field Office	Lump Sum	1.00	
AR152410	Unclassified Excavation	Cubic Yard	2,565.00	
AR156510	Silt Fence	Linear Foot	620.00	
AR156513	Separation Fabric	Square Yard	11,485.00	
AR156520	Inlet Protection	Each	7.00	
AR201611	Bituminous Base Course - Method I	Ton	1,515.00	
AR209612	Crushed Agg. Base Course - 12"	Square Yard	11,570.00	
AR401611	Bit. Surface Course - Method I	Ton	1,400.00	
AR401660	Saw and Seal Bit. Joints	Linear Foot	343.00	
AR401665	Bituminous Pavement Sawing	Linear Foot	343.00	
AR401900	Remove Bituminous Pavement	Square Yard	11,580.00	
AR402620	Porous Friction Course, 5/8"	Square Yard	11,485.00	
AR602510	Bituminous Prime Coat	Gallon	3,471.00	
AR603510	Bituminous Tack Coat	Gallon	4,610.00	
AR620520	Pavement Marking - Waterborne	Square Foot	4,010.00	
AR705412	Porous Backfill No. 2	Cubic Yard	225.00	
AR705506	6" Perforated Underdrain	Linear Foot	2,951.00	
AR705630	Underdrain Inspection Hole	Each	2.00	
AR705640	Underdrain Cleanout	Each	4.00	
AR705900	Remove Underdrain	Linear Foot	2,630.00	
AR705903	Remove Underdrain Insp. Hole	Each	6.00	
AR705904	Remove Underdrain Cleanout	Each	2.00	
AR800937	Conservation Cover	Acre	0.50	
AR800964	Lighted Runway Closure Marker	Each	2.00	
AR800971	Granular Drainage Subbase - 8"	Square Yard	11,485.00	
AR904510	Sodding	Square Yard	5,325.00	
AR905520	Topsoiling (From Off Site)	Cubic Yard	595.00	

SUMMARY OF QUANTITIES - ADDITIVE ALTERNATE NO. 1

Item			Quantity	
Number	Description	Unit	Bid	Paid
AR125941	Adjust Stake Mounted Light	Each	8.00	
AR125942	Adjust Base Mounted Light	Each	4.00	
AR152410	Unclassified Excavation	Cubic Yard	735.00	
AR156513	Separation Fabric	Square Yard	2,440.00	
AR201611	Bituminous Base Course - Method I	Ton	295.00	
AR209612	Crushed Agg. Base Course - 12"	Square Yard	2,440.00	
AR401611	Bit. Surface Course - Method I	Ton	295.00	
AR401660	Saw and Seal Bit. Joints	Linear Foot	270.00	
AR401665	Bituminous Pavement Sawing	Linear Foot	270.00	
AR401900	Remove Bituminous Pavement	Square Yard	2,440.00	
AR602510	Bituminous Prime Coat	Gallon	732.00	
AR603510	Bituminous Tack Coat	Gallon	366.00	
AR620520	Pavement Marking - Waterborne	Square Foot	1,570.00	
AR620525	Pavement Marking - Black Border	Square Foot	174.00	
AR705412	Porous Backfill No. 2	Cubic Yard	60.00	
AR705506	6" Perforated Underdrain	Linear Foot	805.00	
AR705640	Underdrain Cleanout	Each	3.00	
AR705900	Remove Underdrain	Linear Foot	825.00	
AR705903	Remove Underdrain Insp. Hole	Each	3.00	
AR705904	Remove Underdrain Cleanout	Each	3.00	
AR800971	Granular Drainage Subbase - 8"	Square Yard	11,485.00	
AR904510	Sodding	Square Yard	1,940.00	
AR905520	Topsoiling (From Off Site)	Cubic Yard	215.00	

No.	Drawing Issue Description	Date	By	

Date
JUNE 18, 2007
Sheet Title

SUMMARY OF QUANTITIES

840-07B8053
Project Number
LDH 06/18/07
Layout By Date
LDH 06/18/07
Designed By Date
RMH 06/18/07
Reviewed By Date
LDH
Drawn By

P:\07\005\00540\07B8053\DRAWINGS\SHEETS\02-QUANTITIES.DWG, JUN 19, 2007 4:35PM BLB