LI030

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	L.F.	1,414	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	17,846	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	308	
AR402622	POROUS FRICTION COURSE, 0.10'	S.Y.	17,846	
AR510510	TIE DOWN	EA	14	
AR510900	REMOVE TIE DOWN	EA	29	
AR510905	REMOVE GROUND ROD	EA	6	
AR603510	BITUMINOUS TACK COAT	GAL.	5,355	
AR620520	PAVEMENT MARKING – WATERBORNE	S.F.	824	
AR620525	PAVEMENT MARKING – BLACK BORDER	S.F.	202	
AR751940	ADJUST INLET	EA.	2	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED STAGING PLAN STA. 8+00 TO STA. 13+25
5	PROPOSED STAGING PLAN STA. 13+25 TO STA. 17+00
6	PROPOSED CONSTRUCTION PLAN STA. 8+00 TO STA. 13+25
7	PROPOSED CONSTRUCTION PLAN STA. 13+25 TO STA. 18+00
8	PAVEMENT PREPARATION AND CONSTRUCTION PLAN NOTES
9	EXISTING TIE DOWN LAYOUT PLAN STA 8+00 TO STA. 13+25
10	EXISTING TIE DOWN LAYOUT PLAN STA. 13+25 TO STA. 18+00
11	PROPOSED TIE DOWN LAYOUT PLAN STA. 8+00 TO STA. 13+25
12	PROPOSED TIE DOWN LAYOUT PLAN STA. 13+25 TO STA. 18+00
13	PROPOSED APRON MARKING PLAN STA. 8+00 TO STA. 13+25
14	PROPOSED APRON MARKING PLAN STA. 13+25 TO STA. 18+00

DATE	REVISION	BY

LITCHFIELD MUNICIPAL AIRPORT
LITCHFIELD, ILLINOIS

IL. PROJ.: 3LF-3645 A.I.P. PROJ.: 3-17-0063-B14

HEI Project No. 814-07APND
Filename R-002FLP.DWG
Scale NOT TO SCALE
Date 02/01/07

LAYOUT	Z.S.H.	02/01/07
DRAWN	Z.S.H.	02/01/07
REVIEWED	C.A.H.	05/09/07

HANSON
Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2888
Offices Nationwide

P.F.C. OVERLAY
AIRCRAFT APRON

SUMMARY OF QUANTITIES
AND
INDEX TO SHEETS

JUN 08, 2007 9:54 AM CAH
J:\AIRPORTS\LITCHFIELD\814-07APN\AIRPORT\SHEETS\R-002FLP.DWG - Layout1