

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE									
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD			
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY		
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	108,702	108,702									
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SO YD	73,153	73,153									
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	608	200									408 +
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	390	390									
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	22						22				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,225	1,923					2,302				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	437	39									398 +
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SO YD	18,966	18,966									
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SO YD	6,058	6,058									
42000541	PORTLAND CEMENT CONCRETE PAVEMENT 12" (JOINTED)	SO YD	68,449	43,984					24,465				
42001300	PROTECTIVE COAT	SO YD	20,017	20,017									
44000100	PAVEMENT REMOVAL	SO YD	69,793	65,508					4,285				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	519	519									
44000300	CURB REMOVAL	FOOT	954	292					662				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1367						1367				

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbda-inc.com



+ 80% STATE / 20% LOCAL  
\* SPECIALTY ITEMS

FILE NAME - 4FILE54	USER NAME - default	DESIGNED - JMG	REVISED -
		DRAWN - JMG	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 6/19/2012	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 3 OF 29 SHEETS STA. NA TO STA. NA

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1-R-1	LAKE	677	6
CONTRACT NO. 60L77				

Rev. 7-23-12

S:\1181\05\_1200-60L77\_IL\_173\60L77\_Sheets\0506L77-341-000.dgn