

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				90% FEDERAL, 10% STATE				100% ISTHA			100% LOCAL NTFPD		
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY		
50200100	STRUCTURE EXCAVATION	CU YD	1,348				700		648				
50300225	CONCRETE STRUCTURES	CU YD	645.3		80.8				564.5				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,776		1,736		40						
50300260	BRIDGE DECK GROOVING	SO YD	2,960		2,960								
50300280	CONCRETE ENCASEMENT	CU YD	30						30				
50300300	PROTECTIVE COAT	SO YD	4,825		4,825								
50400745	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 72"	FOOT	4,757						4,757				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	487,160	1500	416,220		5,320		64,120				
50800515	BAR SPLICERS	EACH	1,322		1,220				102				
50901720	BICYCLE RAILING	FOOT	132				132						
50901735	BRIDGE FENCE RAILING (SIDEWALK)	FOOT	626		522							104**	
50901750	PARAPET RAILING	FOOT	618		475							143**	
54010704	PRECAST CONCRETE BOX CULVERTS, 7' X 4"	FOOT	213						213				
51100100	SLOPEWALL 4 INCH	SO YD	1,566		87				1,479				
51201800	FURNISHING STEEL PILES HP14X73	FOOT	7,302						7,302				

** THIS ITEM IS 100% LCDOT, CCS CODE 010, BRIDGE SN 049-0535
 • SPECIALTY ITEMS

BOWMAN, BARRETT & ASSOCIATES INC.
 CONSULTING ENGINEERS
 Chicago, Illinois
 312.228.0100
 www.bbainc.com

FILE NAME - #FILES#	USER NAME - default	DESIGNED - JMG	REVISED -
		DRAWN - JMG	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 6/19/2012	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 5 OF 29 SHEETS STA. NA TO STA. NA

P.A. RTE. 94	SECTION 49-1-R-1	COUNTY LAKE	TOTAL SHEETS 677	SHEET NO. 8
CONTRACT NO. 60L77			ILLINOIS FED. AID PROJECT	

Rev. 7-23-12

S:\101025_0000\80-27 IL 173\80-27 Sheets\1182-27-101-0000.dwg