

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE								
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD		
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY	
55101200	STORM SEWER REMOVAL 24"	FOOT	120	8					112			
58700300	CONCRETE SEALER	SO FT	5,084							5,084		
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	280							280		
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	38	38								
60107700	PIPE UNDERDRAINS 6"	FOOT	17,404	17,404								
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	2,836	1,093					1,743			
60109520	PIPE UNDERDRAINS, FABRIC LINED TRENCH 6"	FOOT	15,213						15,213			
60200105	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	4	4								
60200805	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 8 GRATE	EACH	6	6								
60201310	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 20 FRAME AND GRATE	EACH	3	3								
60218400	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	5					1			
60219000	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 8 GRATE	EACH	1	1								
60221700	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 8 GRATE	EACH	1	1								
60255500	MANHOLES TO BE ADJUSTED	EACH	3						3			
60500050	REMOVING CATCH BASINS	EACH	6	3					3			

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbandainc.com



• SPECIALTY ITEMS

△ Rev. 7-23-12

FILE NAME - #FILES#	USER NAME - default	DESIGNED - JMC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE. 94	SECTION 49-1-R-1	COUNTY LAKE	TOTAL SHEETS 677	SHEET NO. 11			
	PLOT SCALE - 1/4"=1'-0"	DRAWN - JMC	REVISED -			SCALE: NA	SHEET NO. 8 OF 29 SHEETS	STA. NA	TO STA. NA	CONTRACT NO. 60L77			
	PLOT DATE - 6/19/2012	CHECKED - RCR	REVISED -			ILLINOIS FED. AID PROJECT							
		DATE - 6/19/2012	REVISED -										

S:\1181\02\_CADD\508.77\_IL\_173462.77\_Sheets\1181\60L77-101-1000.dgn