

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				90% FEDERAL, 10% STATE				100% ISTHA			100% LOCAL NTFPD	
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY	
*78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	264			177					87	
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,130			1,105					25	
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	18			18						
*78100300	REPLACEMENT REFLECTOR	EACH	10			10						
*78200300	PRISMATIC CURB REFLECTOR	EACH	144			144						
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	72			35					37	
*78200530	BARRIER WALL MARKERS, TYPE C	EACH	12,898			8,205					4,693	
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	13			5					8	
78300100	PAVEMENT MARKING REMOVAL	SO FT	19,473			19,473						
•80400100	ELECTRIC SERVICE INSTALLATION	EACH	3			3						
•80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1			1						
•80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2			2						
•81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	4,329			4,329						
•81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	248			248						

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



• SPECIALTY ITEMS

FILE NAME - #FILES#	USER NAME - default	DESIGNED - JMG	REVISED -
		DRAWN - JMG	REVISED -
PLOT SCALE - 1/4"=1'-0" V=1'-0"		CHECKED - RGR	REVISED -
PLOT DATE - 6/19/2012		DATE - 6/19/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 13 OF 29 SHEETS STA. NA TO STA. NA

F.A. RTE. 94	SECTION 49-1-R-1	COUNTY LAKE	TOTAL SHEETS 677	SHEET NO. 16
CONTRACT NO. 60L77				
[ILLINOIS] FED. AID PROJECT				

S:\118105\000062.77 IL 173-88271 Sheets\0862.77-11-13-12.dgn