

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				90% FEDERAL, 10% STATE				100% ISTHA		100% LOCAL NTFPD			
				0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0040 RETAINING WALL SN 049-W045	0003 ROADWAY	0010 BRIDGE SN 049-0535	0021 SAFETY	0021 SAFETY		
			<i>URBAN</i>										
• 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	2400			2400							
• 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1,147			947						200	
• 81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	80								80		
• 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	1,103			1,103							
• 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	325			325							
• 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	463			463							
• 81200270	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC	FOOT	401			207					194		
• 81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	14			14							
• 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	20			20							
• 81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	2			2							
• 81400100	HANDHOLE	EACH	10			4					6		
• 81400200	HEAVY-DUTY HANDHOLE	EACH	13			13							
• 81400300	DOUBLE HANDHOLE	EACH	4			4							
• 81603081	UNIT DUCT, 600V (XLP-TYPE USE), 1 1/2" DIA. PIA POLYETHYLENE	FOOT	3,616			3,616							

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



• SPECIALTY ITEMS

FILE NAME - 4FILES*	USER NAME - default	DESIGNED - JMG	REVISED -
		DRAWN - JMG	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 6/19/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 14 OF 29 SHEETS STA. NA TO STA. NA

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	49-1-R-1	LAKE	677	17
CONTRACT NO. 60L77				
ILLINOIS FED. AID PROJECT				

S:\1101\05-CAD\0508-77 IL 173\60L77 Sheet 17 of 18.dwg